

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		SE 1/4 NW 1/4 NW 1/4	29	T 18 S	R 15 E/W
Distance and direction from nearest town or city street address of well if located within city? 1/2 mile north of Albert, Ks.					
2 WATER WELL OWNER:		Elmer Mausolf			
RR#, St. Address, Box # :		Albert, Ks. 67511		Board of Agriculture, Division of Water Resources	
City, State, ZIP Code :				Application Number: 5365	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 102 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL . . . 28 ft. below land surface measured on mo/day/yr . . . 10-18-90			
		Pump test data: Well water was . . . 58 1/2 ft. after hours pumping . . . 1400 . . . gpm			
		Est. Yield . . 1400 . . gpm: Well water was . . . 48 1/2 ft. after . . . 2 hours pumping . . . 900 . . . gpm			
		Bore Hole Diameter . . . 30 . . . in. to . . . 102 ft. and in. to ft.			
WELL WATER TO BE USED AS:		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> If yes, mo/day/yr sample was submitted		Water Well Disinfected? Yes <u>h+h</u> No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued <u>X</u> Clamped			
1 Steel 3 RMP (SR)		Welded			
2 PVC 4 ABS		Threaded			
Blank casing diameter 16 in. to . . . 62 ft. Dia in. to ft. Dia in. to ft.					
Casing height above land surface 12 in., weight . . . SDR 32.5 lbs./ft. Wall thickness or gauge No.					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		11 Other (specify)			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From . . . 62 ft. to . . . 102 ft. From ft. to ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From . . . 20 ft. to . . . 49 ft. From . . . 52 ft. to . . . 102 ft. From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other hole plug 49 to 52'					
Grout Intervals: From . . . 0 ft. to . . . 20 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage none					
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Top soil			
3	30	Black clay			
30	31 1/2	Sand with clay mixed			
31 1/2	49	Sand and gravel			
49	52	Clay			
52	53 1/2	Sand and gravel			
53 1/2	58	Clay			
58	60	Sand and gravel			
60	61	Clay			
61	85 1/2	Sand and gravel			
85 1/2	91	Clay			
91	100	Sand and gravel			
100	102	Clay			
102	105	Fire clay			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-19-90 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. . . . 134 This Water Well Record was completed on (mo/day/yr) . . . 11-20-90					
under the business name of Rosencrantz-Breis by (signature) <i>Gredia Rodson</i>					