


1 LOCATION OF WATER WELL: Fraction NE 1/4 NE 1/4 NE 1/4 Section Number 5XX Township Number T 18 XX S Range Number R 21 EW

Distance and direction from nearest town or city street address of well if located within city? 2 miles East and 5 mile North of Bazine, Ks. 67516

2 WATER WELL OWNER: HARRY JANKE RR#, St. Address, Box # RT. 1 BOX 94 City, State, ZIP Code : McCracken, Ks. 67556 Board of Agriculture, Division of Water Resources Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:



4 DEPTH OF COMPLETED WELL: 39 ft. ELEVATION: UPLAND

Depth(s) Groundwater Encountered 1. 20 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL . 20 . ft. below land surface measured on mo/day/yr JANUARY 19, 1989. Pump test data: Well water was . 30 . ft. after . 1/2 . hours pumping . 5 . gpm Est. Yield . 8 . gpm: Well water was . ft. after . hours pumping . gpm Bore Hole Diameter . . 8 . in. to . 39 . ft., and . in. to . ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes. No. XX; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes XX No

5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued XX Clamped Welded Threaded 2 PVC 4 ABS 7 Fiberglass 9 Other (specify below)

Blank casing diameter . . 5 . in. to . 19 . ft., Dia . in. to . ft., Dia . in. to . ft. Casing height above land surface . . 12 . in., weight 2.87 lbs./ft. Wall thickness or gauge No. . 256"

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)

SCREEN-PERFORATED INTERVALS: From . 19 . ft. to . 39 . ft., From . ft. to . ft. GRAVEL PACK INTERVALS: From . 18 . ft. to . 39 . ft., From . ft. to . ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From . 0 . ft. to . 18 . ft., From . ft. to . ft., From . ft. to . ft.

What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? NORTH How many feet? 60

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows show soil layers: black topsoil (0-4), brown clay (4-15), light green clay (15-28), sand & clay (28-30), black shale (30-39).

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) JANUARY 19, 1989 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 243 This Water Well Record was completed on (mo/day/yr) JANUARY 19, 1989 under the business name of DEAN WATERHOUSE DRILLING by (signature) Dean Waterhouse