

134

HYDRAULIC DRILLING COMPANY

216 E. PACIFIC
PHONE 7-1532
NIGHT PHONE 6692



SALINA, KANSAS
Box 477

LOG OF WELL

NAME W. R. Ramsey HOLE NO. 1 DATE DRILLED 11-9-53
LOCATION NW NW Sec. 28 T18S. R 3E, Matherson Co.
About 50' E. of house
TYPE OF WELL Domestic TOPOGRAPHY top hill, dissected upland
DEPTH 109 FEET. DIAM. OF HOLE 6 INCHES. DEPTH TO WATER 49 FEET
CASING: 4" OD, 4" ID steel, lower 10 ft. has 3/16" round openings
YIELD Failed 7.5 gpm with water at 65 ft. below land surface
REMARKS Well will probably need sand boiling occasionally

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
Silt and clay, gray and buff	6	6	
Silt and clay, compact, buff	49	55	
Silt and clay, white and buff; contains caliche, nodular	23	78	
Silt, soft, light gray and buff, contains much sand, fine to medium	25.5	103.5	
Sand, fine to coarse and gravel, fine; Hard cemented zone at top	3	106.5	
Clay, compact	3	109	

W.R. Ramsey
7717 Ward Parkway
K.C. 14, Missouri
Phone - Highland 4-0463
17.110 R.O. Total