

L A T T A A N D F E N T

102½ N. SANTA FE
PHONE 2717~~SALINA~~, KANSAS
Box 720WATER WELLS
TEST HOLES3 OF WELLNAME Leonard Larson HOLE NO. 1 DATE DRILLED Sept. 1, 1948LOCATION NW¼ sec. 20 T. 18S, R. 5W, McPherson CO.About 500 feet east of house at fence line.TYPE OF WELL test TOPOGRAPHY _____DEPTH 70 FEET. DIAM. OF HOLE 4 INCHES. DEPTH TO WATER 16.2 FEET

CASINGS DIAM. _____ INCHES. SET AT _____ FEET. FINISH _____

YIELD _____

REMARKS _____

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
Soil	2	2	
Silt clay; cream-tan, gray, and tan; contains caliche nodules	43	45	Slow
Silt and sand, fine	2.5	47.5	Faster
Sand, fine to medium	2.5 ²²	50	Very fast
Sand, fine to medium, containing some coarse sand and a little fine gravel; alternating with beds of sandy silt	16 ²²	66	Very fast and slow, alt.
Sand, fine to coarse, containing fine to medium gravel	2 ⁷⁰	68	Very fast
Sand, fine to medium, and silt	1.5 ⁴⁰	69.5	Fast and slow
Ferrian Shale, red	0.5	70	<u>Slow</u>