

WATER WELL RECORD Form WMC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: * | Fraction | Section Number | Township Number | Range Number
 COUNTY: 086 SCOTT | SW 1/4 NW 1/4 NE 1/4 | 18 | T 18 S | R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 1ST AND ANTELOPE SCOTT CITY, KS 67213-

2 WATER WELL OWNER: SCOTT COOP ASSOCIATION
 RR#, St. Address, Box #: P.O. BOX 340 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SCOTT CITY, KS 67871- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 150 | ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 123 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 123 ft. below land surface measured on mo/day/yr 06/04/91
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8 in. to 150 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 10 MONITORING
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: THREADED
 Blank casing diameter 2 in. to 100 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface -4 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 100 ft. to 150 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 89 ft. to 150 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 89 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 11 FUEL STORAGE
 Direction from well? LOCAL AREA How many feet? 01

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	05 SAND			* 275' west and 30' south of the southeast corner of the building at 1 st and Antelope.
10	20	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
20	45	03 SILTY CLAY			
45	56	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
56	97	01 CLAY			
97	101	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
101	107	01 CLAY			
107	140	31 CALICHE 01 CLAY			
140	150	05 SAND 11 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/05/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/31/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas B. Henkle