

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number |
 COUNTY: 086 SCOTT | SE 1/4 NW 1/4 SW 1/4 | 18 | T 18 S | R 23 W

Distance and direction from nearest town or city street address of well if located within city?
 1ST & COLLEGE SCOTT CITY, KS 67871-

2 WATER WELL OWNER: SCOTT COOPERATIVE ASSOC. MW #6
 RR#, St. Address, Box #: P. O. BOX 340 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SCOTT CITY, KS 67871- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 155 | ELEVATION: 0 |
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 131 ft. below land surface measured on mo/day/yr 11/05/92
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter in. to 155 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 10 MONITORING
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: THREADED
 Blank casing diameter 4 in. to 155 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface -4 in., weight 2 lbs/ft. Wall thickness or gauge No. .237
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 115 ft. to 155 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 105 ft. to 155 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 105 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 11 FUEL STORAGE
 Direction from well? LOCAL AREA How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	01 CLAY			
5	20	01 CLAY 05 SAND			
20	55	01 CLAY			
55	85	05 SAND 13 FINE GRAVEL			
85	105	31 CALICHE			
105	125	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
125	140	31 CALICHE			
140	150	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
150	155	23 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 11/10/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/15/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) Bruce J. Reichmuth