

1 LOCATION OF WATER WELL: Fraction NW 1/4 NE 1/4 SE 1/4 Section Number 13 Township Number T 18 S Range Number R 33 EW  
 County: Scott

Distance and direction from nearest town or city street address of well if located within city?  
 111 W. Bellvue, Scott City, Ks. 67871

2 WATER WELL OWNER: John Hrbeck  
 RR#, St. Address, Box #: Rt. 1, Box 103 Board of Agriculture, Division of Water Resources  
 City, State, ZIP Code: Scott City, Ks. 67871 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: [Diagram showing a 2x2 grid with NW, NE, SW, SE quadrants. An 'X' is marked in the SE quadrant. A vertical scale on the left indicates 1 Mile.]

4 DEPTH OF COMPLETED WELL: 224' ft. ELEVATION:  
 Depth(s) Groundwater Encountered 1. 127' ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL: 127' ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was ft. after hours pumping gpm  
 Est. Yield gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter: 10" in. to 224' ft., and in. to ft.  
 WELL WATER TO BE USED AS:  
 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)  
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well  
 Was a chemical/bacteriological sample submitted to Department? Yes No ; If yes, mo/day/yr sample was submitted  
 Water Well Disinfected? Yes  No

5 TYPE OF BLANK CASING USED:  
 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped  
 PVC 4 ABS 7 Fiberglass Welded  
 Blank casing diameter: 5" in. to 224' ft., Dia. in. to ft., Dia. in. to ft.  
 Casing height above land surface: 24" in., weight lbs./ft. Wall thickness or gauge No. SCH. 40  
 TYPE OF SCREEN OR PERFORATION MATERIAL:  
 PVC 10 Asbestos-cement  
 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)  
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)  
 SCREEN OR PERFORATION OPENINGS ARE:  
 1 Continuous slot  Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)  
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes  
 7 Torch cut 10 Other (specify)  
 SCREEN-PERFORATED INTERVALS: From 204' ft. to 224' ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From 20' ft. to 224' ft., From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout  Bentonite 4 Other  
 Grout Intervals: From 0 ft. to 20' ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination:  
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens  Abandoned water well  
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well  
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)  
 13 Insecticide storage PLUGGED & SEALED  
 Direction from well? SouthEast How many feet? 50'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Top Soil	207	212	Yellow Clay
1	6	Sandy Clay	212	222	Blue Shale
6	13	Very Fine Sand		224	Total Depth
13	16	Sandy Clay			
16	38	Tan Clay Sticky			
38	55	Tan Sandy Clay			
55	74	Medium Sand, Loose Small Clay Streaks			
74	106	Tan Clay Sticky			
106	123	Clay w/Limestone Streaks on Fine Sand Streaks			
123	132	Fine to Medium Sand, Clay Streaks			
132	195	Coarse Sand, Loose Sm. Gravel Some Small Clay Streaks			
195	198	Sandy Clay, Sand Streaks			
198	207	Coarse Sand, Small Gravel Loose			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was  constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 09/30/89 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. #514. This Water Well Record was completed on (mo/day/yr) 12/18/89 under the business name of Miller Gearhead & Pump Repair Inc. by signature *Everett Miller*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320. Telephone: 913-296-5514. Send one to WATER WELL OWNER and retain one for your records.