

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: SCOTT | SW 1/4 NW 1/4 SW 1/4 | 14 | T 18 S | R 34 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 1/2 MILES EAST OF NODOC

2 WATER WELL OWNER: SCOTT COUNTY FEEDERS INC.
 RR#, St. Address, Box #: ROUTE 3, BOX 151A Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SCOTT CITY, KS 67871- Application Number: 29655

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 175 ELEVATION:
 Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL: 124 ft. below land surface measured on mo/day/yr 01/03/91
 Pump test data: Well water was 157 ft. after 4 hours pumping 91 gpm
 Estimated Yield 90 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 17.5 in. to 175 ft., and in. to ft.
 WELL WATER TO BE USED AS: FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 8 in. to 175 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 6 lbs/ft. Wall thickness or gauge No. .410
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: MILL SLOT

SCREEN PERFORATED INTERVALS: From ft. to ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 175 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? WEST How many feet? 256

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
2	2	TOP SOIL /			
2	49	BRN SANDY CLAY/ LIMEROCK / FINE SAND STKS/			
49	100	SAND FN-MD CRS/ SMALL GRAVEL /			
100	105	BRN SANDY CLAY/ CEMENTED SAND / LAYERS /			
105	135	SAND FN-MD CRS/ SMALL GRAVEL /			
135	140	BRN SANDY CLAY/ WITH CEMENTED SAND /			
140	144	SAND FINE-MED /			
144	155	YELLOW CLAY / SOME SAND STREAKS /			
155	161	SAND FN-MD CRS/ WHITE ROCK /			
161	164	SOAPSTONE /			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 01/03/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/14/91 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce J. Reichmuth

