

MODOC

1834W31CAD
T R EW sec 1/4 1/4 1/4 No.

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

CAD

1 Location of well:	County Scott	Township name	Fraction SE-NE-SW	Section number 31	Town number 18 S	Range number 34 W
Distance and direction from nearest town or city: 1/2 W, 2 1/2 S, 1/2 E of C of Scott City			3 Owner of well: W.N. Robinson Address: 105 E. 1st St. Scott City, Ks. 67871			
Locate with "X" in section below:		Sketch map:		4 Well depth: 140 ft. Date of completion 6-19-75 Well diameter 9 3/8 in.		
				5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
				6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well		
				7 Casing: Material ABS Height: <input type="checkbox"/> Above <input checked="" type="checkbox"/> Below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. 5 in. to 120 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No 7 lbs./ft. Weight 1250 well in. to 140 ft. depth		
2 Type and color of material		From	To	8 Screen: Manufacturer Jess & Lowell Type ABS Dia. 5" I.D. Slot gauge 110 Length 20ft. Set between 120 ft. and 140 ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 58-low		
clay and soil		0	32	9 Static water level: 105 ft. below land surface Date 4-21-75		
sandstone and gyp.		32	46	10 Pumping level below land surfaces: 138 ft. after 2 hrs. pumping 50 g.p.m. ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 50 g.p.m.		
sand with some clay		46	63	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____		
sand with gyp.		63	81	12 Well head completion: <input checked="" type="checkbox"/> Pitless adapter unit <input type="checkbox"/> Inches above grade		
sand, some gyp + clay, loose gravel		81	110	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From 0 ft. to 20 ft.		
rock and gyp. with hard gravel		110	114	14 Nearest source of possible contamination: ft 2000 Direction North Type septic tank Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
sand with some clay		114	137	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name Goulds Model number 36255029 5 Volts 220 Length of drop pipe 135 ft. capacity 20 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
yellow		137	140	16 Remarks: elevation 3163 (TOPO)		
		(use a second sheet if needed)		17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. ABC Drilling Co. 246 Business name License No. Address Scott City, Ks. 67871 Signed Don Nottingham Date 7-5-75 Authorized representative		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5