

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

MARIENTHAL

BBC

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Scott	Fraction SW 1/4 NW 1/4 NW 1/4	Section number 31	Township number T 18 S R 34 NE/W	Range number
2. Distance and direction from nearest town or city: Scott City 12 miles west; 2 1/4 miles south; 50 yards east			3. Owner of well: W. N. Robinson III (Robinson Farms) R.R. or street: 105 E. First St. City, state, zip code: Scott City, KS 67871			
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. <u>12</u> in. Completion date <u>10-31-76</u> Well depth <u>138</u> ft.	
					7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Dirt and soil		0	24	9. Casing: Material <u>PVC</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight _____ lbs./ft. Dia. <u>5</u> in. to <u>118</u> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <u>0.265</u>		
Gyp (caliche)		24	32	10. Screen: Manufacturer's name <u>Jess & Lowell</u> Type <u>PVC</u> Dia. <u>5"</u> Slot/gauze <u>1/8"</u> Length <u>20'</u> Set between <u>119</u> ft. and <u>138</u> ft. _____ ft. and _____ ft. Gravel pack? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>1/2" down</u>		
Sandy clay		32	46	11. Static water level: _____ mo./day/yr. <u>114</u> ft. below land surface Date <u>10-15-76</u>		
Sand		46	68	12. Pumping level below land surfaces: <u>136</u> ft. after <u>1</u> hrs. pumping <u>30</u> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>30</u> g.p.m.		
Fine gravel		68	132	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____		
Yellow clay		132	137	14. Well head completion: <u>Platform, well seal,</u> <u>pipe to line</u> <input checked="" type="checkbox"/> Pitless adapter _____ inches above grade		
Blue shale		138		15. Well grouted? <u>yes</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10+</u> ft.		
BROOK 132'				16. Nearest source of possible contamination: <u>Irrigation</u> ft. <u>10'</u> Direction <u>north</u> Type <u>water</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: Not installed Manufacturer's name <u>Coulds</u> Model number <u>UTS</u> HP <u>5</u> Volts <u>230</u> Length of drop pipe <u>135</u> ft. capacity <u>30</u> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:	19. Remarks:			20. Water well contractor's certification:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	Tied to 5 or 6 other wells to run sprinkler system <u>3158 (TOPO)</u>			This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>ABC Drilling, Inc. 246</u> Business name License No. Address <u>Scott City, KS 67871</u> Signed <u>Sydney H. Ross</u> Date <u>3/23/77</u> Authorized representative		

T 18 S R 34 NE/W
Sec 31