

1 LOCATION OF WATER WELL: COUNTY: 102 WICHITA	Fraction SE 1/4 NE 1/4 SW 1/4	Section Number 17	Township Number T 18 S	Range Number R 36 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM LEOTI; APPX 2 1/2 MILES EAST

2 WATER WELL OWNER: ESE ALCOHOL PLANT *of TAYLOR & Assoc.*
RR#, St. Address, Box #: 509 N. 6TH
City, State, ZIP code : GARDEN CITY, KS 67846-5508

Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL *141* ft. below land surface measured on mo/day/yr *8/14/05*
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

1	NW	NE		
M	W		E	
l				
e	SW		SE	

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 7 1/2 in. to 165 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 10 MONITORING
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: *THREADED*

Blank casing diameter 4 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 2 lbs/ft. Wall thickness or gauge No. .237

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 145 ft. to 165 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 140 ft. to 165 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 140 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: *NONE OBSERVED*

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	38	04 SANDY CLAY			
38	57	05 SAND			
57	62	31 CALICHE			
62	108	05 SAND 01 CLAY			
108	149	05 SAND			
149	163	05 SAND			
163	170	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/14/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/13/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Brian J. Henkle*