

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Wichita</b>	Fraction <b>NW 1/4 <del>SW</del> 1/4 SW 1/4</b>	Section number <b>8</b>	Township number <b>T 18 S R 36 E 10</b>	Range number
2. Distance and direction from nearest town or city: <b>23W, 1 1/2 N, 500' E</b>			3. Owner of well: <b>Mike Schump</b>			
Street address of well location if in city: <b>of Scott City, Kansas</b>			R.R. or street: <b>3505 Seeley Court</b>			
			City, state, zip code: <b>Greeley, Colorado 80631</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>26</u> in. Completion date <u>12-24-76</u>		
		<p style="text-align: center;">X well ↓ 1/2 mi. <u>Septic</u></p>		Well depth <u>191</u> ft.		
				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
				9. Casing: Material <u>Steel</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>10</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>31.67</u> lbs./ft. Dia. <u>16</u> in. to <u>191</u> ft. depth; Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth; gage No. <u>188</u>		
5. Type and color of material		From	To	10. Screen: Manufacturer's name <u>Free Flow</u>		
Clay		0	30	Type <u>Prime Steel</u> Dia. <u>16 in.</u>		
Gyp		30	39	<input checked="" type="checkbox"/> Slot/gauze <u>125</u> Length <u>40 ft.</u>		
Rock H		39	43	Set between <u>151</u> ft. and <u>191</u> ft.		
<del>Rock</del> <del>Rock</del> <del>XXX</del> Gyp		43	54	Gravel pack? <input checked="" type="checkbox"/> yes Size range of material <u>3/4-1/4</u>		
<del>Gyp</del> Clay		54	55	11. Static water level: <u>135</u> ft. below land surface Date <u>11-13-76</u>		
Gyp		55	59	12. Pumping level below land surfaces: <u>176</u> ft. after <u>4</u> hrs. pumping <u>320</u> g.p.m. <u>182</u> ft. after <u>4</u> hrs. pumping <u>390</u> g.p.m. Estimated maximum yield <u>390</u> g.p.m.		
Clay		59	67	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____		
Gyp		67	79	14. Well head completion: <input type="checkbox"/> Pitless adapter _____ inches above grade		
Fine sd clay		79	100	15. Well grouted? <input checked="" type="checkbox"/> yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
Fine sd T		100	108	16. Nearest source of possible contamination: ft. <u>2640</u> Direction <u>South</u> Type <u>Septick</u>		
Fine sd clay		108	116	Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Sd med Good		116	137	17. Pump: <input type="checkbox"/> Not installed		
Fine sd clay		137	146	Manufacturer's name <u>Layne &amp; Bowler</u>		
Sd fine good		146	151	Model number _____ HP _____ Volts _____		
Clay		151	171	Length of drop pipe <u>180</u> ft. capacity <u>390</u> g.p.m.		
Sd coarse (Use a second sheet if needed)		171	181	Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:	19. Remarks: <b>Yellow</b>	181	185	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weishaar Drilling</u> <u>232</u> Business name License No. Address <u>Scott City, KS 67871</u> Signed <u>[Signature]</u> Date <u>1-21-77</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5