

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County	Fraction	Section number	Township number	Range number		
Wichita	NE 1/4	SE 1/4	NE 1/4	1	T 18 S R 38 E 1/4		
2. Distance and direction from nearest town or city: 4W, 3N, 1W, 1/4 S	3. Owner of well: Chas. Whitham						
Street address of well location if in city: of Leoti, KS	R.R. or street: Leoti, KS 67861						
4. Locate with "X" in section below:	Sketch map:						
	<p>1/4 mi. ← X well</p>						
5. Type and color of material	From	To	6. Bore hole dia. 26 in. Completion date 8-18-75 Well depth 192 ft.				
Clay	0	20	7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input checked="" type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary				
Gyp	20	56	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other				
Clay	56	60	9. Casing: Material <input checked="" type="checkbox"/> Steel Height: <input type="checkbox"/> above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 10 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 31.67 lbs./ft. Dia. 16 in. to 192 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 188				
Sd rock	60	65	10. Screen: Manufacturer's name Free Flow Type <input checked="" type="checkbox"/> Prime Steel Dia. 16 in.				
Fine sd clay T	65	98	Slot gauze 125 Length 45 ft. Set between 147 ft. and 192 ft. ft. and <input type="checkbox"/> ft. Gravel pack <input checked="" type="checkbox"/> yes Size range of material 3/4-1				
Sd med	98	102	11. Static water level: 130 mo./day/yr. ft. below land surface Date 7-1-76				
Fine sd clay	102	140	12. Pumping level below land surfaces: 162 ft. after 4 hrs. pumping 500 g.p.m. 176 ft. after 4 hrs. pumping 590 g.p.m. Estimated maximum yield 590 g.p.m.				
Sd coarse	140	159	13. Water sample submitted: mo./day/yr. Yes <input checked="" type="checkbox"/> No Date				
Clay	159	173	14. Well head completion: Pitless adapter 12 Inches above grade				
Sd coarse	173	189	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 15 ft.				
Clay yellow	189	192	16. Nearest source of possible contamination: ft. 1320 Direction W Type Septic Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
Shale	192		17. Pump: Not installed Manufacturer's name Western Land Roller Model number GE HP 40 Volts 460 Length of drop pipe 180 ft. capacity 590 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
(Use a second sheet if needed)						18. Elevation:	19. Remarks:
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weishaar Drilling 232 Business name <input type="checkbox"/> Scott City, KS 67871 License No. Address <input type="checkbox"/> Street <input type="checkbox"/> Box <input type="checkbox"/> Route <input type="checkbox"/> Other Signature <input type="checkbox"/> Authorized representative <input type="checkbox"/> Date Signature <input type="checkbox"/> Authorized representative <input type="checkbox"/> Date Signature <input type="checkbox"/> Authorized representative <input type="checkbox"/> Date	