

102½ N. SANTA FE  
PHONE 2717SALINA, KANSAS  
Box 720WATER WELLS  
TEST HOLESLOG OF WELLNAME Eben Olson HOLE NO. 1 DATE DRILLED 9-13-50  
LOCATION NE ¼ sec. 4 SW 2 T 18S., R 4W., McPherson CO.At NE corner of house.TYPE OF WELL Domestic TOPOGRAPHY Flood plainDEPTH 50 FEET. DIAM. OF HOLE 7½ INCHES. DEPTH TO WATER 17.6 FEET Below L. S.CASINGS DIAM. 5 INCHES. SET AT 50 FEET. FINISH 2½ feet perforated.YIELD Bailed 10 gallons per minute with water level at 28' below L. S.

REMARKS \_\_\_\_\_

DESCRIPTION OF MATERIAL	THICKNESS (FEET)	DEPTH (FEET)	DRILLING CHARACTER & REMARKS
alluvium: Silt, fine sandy, light gray and buff.	22	22	Fairly slow, smooth
Silt, light gray-brown; contains some gravel, fine to medium sand.	8	30	Fairly slow, smooth
Silt and clay, blue-gray.	5	35	Fairly slow, smooth
Gravel, medium to fine and sand some gravel, coarse, interbedded with little silt, gray.	15	<u>50</u>	Fairly fast, slight chatter.