

C. H. Sandahl
 NW SW Sec. 28
 west side of pasture
 Stock

1
 18s.

48

6-29-56
 McPherson

Upland, near alluvium border

66
 4" galvanized. 2 1/2' screen, closed end.
 Bailed 4 gpm with 3' drawdown

57

Top soil	1	1	
Sand, coarse to fine	4	5	
Gravel, coarse to fine and sand	10	15	
Silt and clay, light gray	2.5	17.5	
Gravel, fine to coarse and sand	20.5	38	
Silt, light gray	1	39	
Gravel, medium to coarse	6	45	
Silt and clay, light gray	2	47	
Gravel, coarse to fine and sand	19	66	Thin clay at 56'