

County		Section number		Township number		Range number	
Greeley		26		T 18		S R 40	
1. Location of well:				3. Owner of well:			
Greeley				Ervin Helm			
2. Distance and direction from nearest town or city: 2½ miles east of Tribune, Kansas Street address of well location if in city:				R.R. or street: City, state, zip code: Tribune, Kansas 67879			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 9 in. Completion date _____ Well depth 105 ft. 5/13/79			
				7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
				8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
				<input checked="" type="checkbox"/> Casing: Material plastic Height: Above or below Threaded Welded blue Surface 12 in. RMP <input checked="" type="checkbox"/> PVC Weight 1.8 lbs./ft. Dia. 5 in. to 85 ft. depth Wall Thickness inches or Dia. _____ in. to _____ ft. depth gage No. .250			
5. Type and color of material		From To		10. Screen: Manufacturer's name _____ Jess & Lowell			
clay		0 18		Type RMP Dia. 5"			
rock		18 21		Slot/gauze 1/16" Length 20"			
sand cemented		21 27		Set between 85 ft. and 105 ft.			
gyp		27 36		Gravel pack? yes Size range of material ¼ x 1/8"			
sand		36 43		11. Static water level: _____ mp./day/yr. 86 ft. below land surface Date 5/2/79			
sand rock		43 46		12. Pumping level below land surfaces: NA _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m.			
fine sand with clay streaks		46 80		Estimated maximum yield _____ g.p.m.			
sand rock		80 87		13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____			
fine sand clay		87 97		14. Well head completion: 12 Pitless adapter _____ Inches above grade			
yellow clay		97 105		15. Well grouted? yes With: <input checked="" type="checkbox"/> Neat cement _____ Bentonite _____ Concrete _____ Depth: From 0 ft. to 15 ft.			
shale		105		16. Nearest source of possible contamination: ft. 200' Direction SW Type septic Well disinfected upon completion? Yes _____ No _____			
				17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ____ Submersible _____ Turbine ____ Jet _____ Reciprocating ____ Centrifugal _____ Other _____			
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weishaar Drilling & Supply 232 Business name _____ License No. _____ Address Scott City, Kans. 67871 Signed _____ Date 5/2/79 Authorized representative			

18	40	26	NE	SW	SE
T	R	Sec	1/4	1/4	1/4