

Windom City

5

1-17-50

SE SE sec. 6

19S.

5W

McPherson

0.32 miles west of SE cor. of Sec. 6

test hole

Upland

59

5

24.35

Below L.S.

Bailed 10 gallons per minute.

water sample No 531.

Fill and soil.

2.5

2.5 Fast, smooth

Clay and silt, brown.

3.5

6 Slow, smooth

Iowa Shale:

Marquette member

Sandstone, yellow-brown to white,
medium to fine; interbedded with
some clay, light gray.

5

11 Fairly fast, chatter

Sandstone, medium to fine, white
and brown.

7

18 Fast, chatter

Clay, blue-gray, mottled yellow,
contains few thin limonite streaks

14

32 Slow, occasional chatter

Sandstone, fine, yellow and white
contains few thin clay zones.

6

48 Fast, chatter

Clay, blue-gray.

9

57 Slow, smooth

Windom member

Limestone, Coquinoid.

2

59 Very slow, chatter
(Chuck)