

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction se 1/4 SW 1/4 SW 1/4	Section number 3	Township number T 19 S R 12 E	Range number 12 E
2. Distance and direction from nearest town or city: XXXXXX 4-N 2-3/4-W north side from Ellinwood, Kans.				3. Owner of well: Alfred Rusco R.R. or street: rt. 3 City, state, zip code: Great Bend, Kansas 67530		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 11 in. Completion date 5-16-79 Well depth 105 ft.		
		7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material pvc Height: Above or Below 18 in. Threaded ☐ Welded ☐ Surface ☐ RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 5 1/2 in. to 105 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 258		
5. Type and color of material				From	To	10. Screen: Manufacturer's name CertainTeed
top soil				0	3	Type pvc Dia. 1 1/16 Length 20
clay				3	8	Slot 3/16 1/16 Set between 85 ft. and 105 ft.
fine sand				8	15	Gravel pack? ☒ Size range of material 3/4 3/8
clay				15	28	11. Static water level: 28 ft. below land surface Date 5-16-79
fine sand				28	35	12. Pumping level below land surfaces: 40 ft. after 1 hrs. pumping 20 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 50 g.p.m.
clay				35	46	13. Water sample submitted: ☒ Yes ☐ No Date 5-16-79
soft sandy clay				46	80	14. Well head completion: ☐ Pitless adapter _____ Inches above grade
sand & gravel w/clay mixed				80	93	15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
clay				93	98	16. Nearest source of possible contamination: ft. 900 Direction west Type septic Well disinfected upon completion? ☒ Yes ☐ No
soft sandy clay				98	101	17. Pump: ☒ Not installed
good clean loose sand rock				101	105	Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed Sandy K. [Signature] Date 5-31-79 Authorized representative
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5