


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County BAYTON	Fraction NW 1/4 NW 1/4 NW 1/4	Section number 7	Township number T 19 S R 12 NW	Range number
2. Distance and direction from nearest town or city: 4 N 3 E			3. Owner of well: John Miorandi			
Street address of well location if in city: Great Bend, KS.			City, state, zip code: R3 Great Bend, KS			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 8 in. Completion date 4-1-77 Well depth 173 ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top Soil - Clay		0	150	9. Casing: Material ☐ Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 5 in. to 173 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. Sch 40		
Sand Rock		150	173	10. Screen: Manufacturer's name MPI Type PVC Dia. 5" Slot/gauze 1/16" Length 20 Set between 153 ft. and 173 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/8 - 3/4"		
				11. Static water level: ☐ mo./day/yr. 112 ft. below land surface Date 4-1-77		
				12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 5 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
				14. Well head completion: ☒ Pitless adapter 12 inches above grade		
				15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 4 ft. to 14 ft.		
				16. Nearest source of possible contamination: sewer ft. 60 Direction E Type ☐ Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☐ Not installed Manufacturer's name Goulds Model number 5ES HP 1 1/2 Volts 230 Length of drop pipe 165 ft. capacity 5 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 186 Kelly's Water Well Serv Business name R3 Great Bend, KS License No. Address Kelly Price Date 7-77 Signed Kelly Price Authorized representative		
Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley		1850				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5