

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Garton</u>	Erection <u>SW NE</u> SE 1/4 SW 1/4 NE 1/4	Section number <u>12</u>	Township number T <u>19</u> S R <u>12</u> E/W	Range number
2. Distance and direction from nearest town or city: <u>3 North 1 W</u>			3. Owner of well: <u>Leo Kowaleby</u>			
Street address of well location if in city: <u>of Ellinwood</u>			R.R. or street: City, state, zip code: <u>Ellinwood, KS</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>12 1/4</u> in. Completion date <u>1-4-77</u> Well depth <u>70</u> ft.		
		7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material ☐ Height: Above or below Threaded ☐ Welded ☒ Surface <u>12018</u> in. RMP ☐ PVC ☒ Weight <u>160</u> lbs./ft. Dia <u>63</u> in. to <u>60</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>225</u>		
5. Type and color of material				From	To	10. Screen: Manufacturer's name <u>R+B</u>
<u>Top soil</u>				<u>0</u>	<u>2</u>	Type <u>pvc</u> Dia. <u>6 1/2</u>
<u>Black clay</u>				<u>2</u>	<u>6</u>	Slot/gauge <u>1/16</u> Length <u>28</u>
<u>Brown clay</u>				<u>6</u>	<u>16</u>	Set between <u>30</u> ft. and <u>50</u> ft.
<u>Black + Brown clay</u>				<u>16</u>	<u>30</u>	Gravel pack? ☒ Size range of material <u>1/4-3/8-1/2</u>
<u>Black clay w/ little sand + gravel</u>				<u>30</u>	<u>37</u>	11. Static water level: <u>11</u> ft. below land surface Date <u>1-4-77</u>
<u>Black clay</u>				<u>37</u>	<u>47</u>	12. Pumping level below land surfaces: <u>29</u> ft. after <u>1</u> hrs. pumping <u>12</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>30</u> g.p.m.
<u>Dark sandy clay</u>				<u>47</u>	<u>52</u>	13. Water sample submitted: ☒ Yes ☐ No Date <u>1-4-77</u>
<u>clay</u>				<u>52</u>	<u>70</u>	14. Well head completion: ☐ Pitless adapter <u>18</u> inches above grade
<u>BR ?</u>				15. Well grouted? ☐		
				With: ☐ Neat cement ☐ Bentonite ☒ Concrete		
				Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: <u>1000</u> ft. Direction <u>NE</u> Type <u>oil well</u> Well disinfected upon completion? ☒ Yes ☐ No		
(Use a second sheet if needed)				17. Pump: ☒ Not installed		
				Manufacturer's name <u> </u>		
				Model number <u> </u> HP <u> </u> Volts <u> </u>		
				Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:	19. Remarks:					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz - Barnes</u> Business name <u>Great Bend, KS</u> License No. <u> </u> Address <u>Media Station</u> Date <u>1-5-77</u> Signed <u> </u> Authorized representative
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley						

T 19
 R 12
 E 12
 Sec 12
 SUSUMNE
 1/4 1/4 1/4