


USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction SW 1/4 SW 1/4 SW 1/4	Section number 32	Township number T 19 S	Range number R 12 E
2. Distance and direction from nearest town or city: 1 S.			3. Owner of well: Bernard Musenbrock			
Street address of well location if in city: Great Bend, KS			R.R. or street: R 1 City, state, zip code: Great Bend, KS			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 6 in. Completion date 10-16-76 Well depth 110 ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top Soil - sand		0	27	9. Casing: Material ☐ Height: ☒ Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 2 in. to 110 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. SC 40		
clay		27	40	10. Screen: Manufacturer's name Peerless Type PVC Dia. 2" Slot/gauze 1/8" Length 20' Set between 90 ft. and 110 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/8 - 3/4"		
sand		40	59	11. Static water level: ☐ mo./day/yr. 8 ft. below land surface Date 10-16-76		
Sand - clay		59	80	12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 30 g.p.m.		
Sand - Gravel		80	110	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
				14. Well head completion: ☐ Pitless adapter 12 inches above grade		
				15. Well grouted? ☒ Not installed With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: sewer ft. 65 Direction E Type ☐ Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Kelly's Water Well Ser. 186 Business name R 2 Great Bend, KS License No. 17654 Address 1819 Signed Kelly Price Date 11-16-76 Authorized representative		
Topography: ☐ Hill ☐ Slope ☒ Upland ☒ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5