

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		NE 1/4 NE 1/4 NW 1/4	33	T 19 S	R 13 (W)
Distance and direction from nearest town or city street address of well if located within city? Steve's Conoco 10th & Main Great Bend, Ks.					
2 WATER WELL OWNER:		Steve Boyd			
RR#, St. Address, Box #		1001 Main			
City, State, ZIP Code		Great Bend, Ks. 67530			
		Board of Agriculture, Division of Water Resources Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 15'6" ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 7.59 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 7.59 ft. below land surface measured on mo/day/yr 10-26-95			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 8 1/2" in. to 15'6" ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		8 Concrete tile			
2 PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)			
5 Fiberglass		Welded X			
Blank casing diameter 2.375 in. to 5' ft., Dia		Threaded SDR 13			
Casing height above land surface Flush Mt. in., weight lbs./ft. Wall thickness or gauge No.		SCH 40			
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)		12 None used (open hole)			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 15' ft. to 5' ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From 15'6" ft. to 4' ft. From ft. to ft.					
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other			
Grout Intervals: From 4' ft. to 3' ft. From 3' ft. to 0' ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? East South East		How many feet? 100'			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	.75	Concrete w/ sand underlayment.			
.75	4	Dk gray silty clay, moist, med plasticity, noodor, mottled.			
4	5	Tan sandy clay, moist, noodor.			
5	8	Gray silty sand, faint odor,			
8	11	Gray -blk fine -coarse grained sand & gravel, moist to wet at 9 1/2' subrounded, poorly sorted.			
11	12	Gray clay, wet, highly plastic, odor.			
12	15'6"	Fine-coarse grained sand & gravel, wet, odor, subrounded w/ clay len at 13' (4" thick). Poorly sorted.			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-25-95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539 This Water Well Record was completed on (mo/day/yr) 10-31-95 under the business name of JB Environmental Drilling by (signature) James Bueker					