


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Barton</u>	Fraction <u>NE 1/4 NE 1/4 SE 1/4</u>	Section number <u>8</u>	Township number <u>T 19 S R 13 E/W</u>	Range number
2. Distance and direction from nearest town or city: <u>3 mi. West Bend, Ks</u> Street address of well location if in city:			3. Owner of well: <u>Steve Haslam</u> R.R. or street: <u>3220 18th St.</u> City, state, zip code: <u>West Bend, Ks.</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>9</u> in. Completion date <u>6-21-76</u> Well depth <u>95</u> ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Top soil</u>		<u>0</u>	<u>2</u>	9. Casing: Material <u> </u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>15</u> in. RMP ☐ PVC ☒ Weight <u>160</u> lbs./ft. Dia. <u>4</u> in. to <u>95</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>Y4</u>		
<u>Black & Brown clay</u>		<u>2</u>	<u>20</u>	10. Screen: Manufacturer's name <u>R+B</u> Type <u>perc</u> Dia. <u>4</u> Slot/gauge <u>1/16</u> Length <u>12</u> Set between <u>82</u> ft. and <u>94</u> ft. <u> </u> ft. and <u> </u> ft.		
<u>Sand & gravel</u>		<u>20</u>	<u>42</u>	Gravel pack? ☒ Size range of material <u>3/4-2</u>		
<u>Brown clay</u>		<u>42</u>	<u>52</u>	11. Static water level: <u> </u> mo./day/yr. <u>22</u> ft. below land surface Date <u>6-21-76</u>		
<u>Sand & gravel</u>		<u>52</u>	<u>57</u>	12. Pumping level below land surfaces: <u>N/A</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.		
<u>Brown clay</u>		<u>57</u>	<u>77</u>	13. Water sample submitted: <u> </u> mo./day/yr. ☒ Yes ☐ No Date <u>6-21-76</u>		
<u>Sand & gravel clay streaks</u>		<u>77</u>	<u>82</u>	14. Well head completion: <u> </u> <u> </u> Pitless adapter <u>18</u> inches above grade		
<u>Sand & gravel</u>		<u>82</u>	<u>94</u>	15. Well grouted? <u> </u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>16</u> ft.		
<u>Brown clay</u>		<u>94</u>	<u>95</u>	16. Nearest source of possible contamination: ft. <u>150</u> Direction <u>East</u> Type <u>septic tank</u> Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Reservoir - Bern's 134</u> Business name <u> </u> License No. <u> </u> Address <u>West Bend, Ks</u> Signed <u>Freddie Rodson</u> Date <u>7/15/76</u> Authorized representative		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☒ Slope ☒ Upland ☐ Valley		<u>1850</u>				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5