


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction SE 1/4 SW 1/4 SE 1/4	Section number 16	Township number T 19 S	Range number R 13 E
2. Distance and direction from nearest town or city: 1 1/2 miles North of Great Bend, KS Street address of well location if in city:			3. Owner of well Barton Co. Rural Water Dist. #2 R.R. or street: Box 916 City, state, zip code: Great Bend, KS 67530			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 28 in. Completion date 12-7-76 Well depth 76 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
top casing to natural ground		0	4	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 49" in. RMP ☐ PVC ☐ Weight 62658 lbs./ft. Dia 16 in. to 41 ft. depth Wall Thickness: inches or Dia 16 in. to 73 ft. depth gage No. 375		
top soil		4	6	10. Screen: Manufacturer's name Doerr # 304 STAINLESS Type Double-slot Dia. 16" Slot gauze 1/16" Length 25' Set between 47 ft. and 69 ft. ft. and ft. Gravel pack? yes Size range of material 3/8-200		
brown clay & silt		6	20	11. Static water level: mo./day/yr. 12'0" ft. below land surface Date 12-7-76		
sand & gravel		20	27	12. Pumping level below land surfaces: 63 ft. after 8 hrs. pumping 1800 g.p.m. 20 ft. after 4 hrs. pumping 350 g.p.m. Estimated maximum yield 1800 g.p.m.		
sand, gravel & clay streaks		27	35	13. Water sample submitted: mo./day/yr. Yes ☒ No ☐ Date		
sand & gravel		35	68	14. Well head completion: ☐ Pitless adapter 49" inches above grade		
brown clay		68	76	15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 20 ft.		
				16. Nearest source of possible contamination: ft. Direction Type Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: Not installed Manufacturer's name Peerless Pump Model number 10LB-6 HP 50 Volts 460 Length of drop pipe 50 ft. capacity 400 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Equip., Inc 185 Business name License No. Address Great Bend, KS 67530 Signed V.W. Clarke Date 12-29-76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5