

1 LOCATION OF WATER WELL: County: Barton	Fraction <i>Ne</i> 1/4 <i>Ne</i> 1/4 S 1/2 1/4	Section Number 19	Township Number T 19 S	Range Number R 13 E/W
---	---	----------------------	---------------------------	--------------------------

Distance and direction from nearest town or city street address of well if located within city?

At 2401 Rockbridge Road, Twin Lakes 2, Lot 14, Block 1

2 WATER WELL OWNER: Ron Royer	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : City, State, ZIP Code : Otis, KS 67565	Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 72 ft. ELEVATION: unknown
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL 14.6 ft. below land surface measured on mo/day/yr 6-25-93
	Pump test data: Well water was not ch'd ft. after hours pumping gpm
	Est. Yield unknown gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter 9 in. to 70 ft., and in. to ft.
WELL WATER TO BE USED AS:	
1 Domestic	3 Feedlot
2 Irrigation	4 Industrial
5 Public water supply	8 Air conditioning
6 Oil field water supply	9 Dewatering
7 Lawn and garden only	10 Monitoring well
11 Injection well	12 Other (Specify below)
Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes No X	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter 5 in. to 50 ft., Dia	in. to ft., Dia	in. to ft.	Threaded
Casing height above land surface 24 in., weight 2.36 lbs./ft.	Wall thickness or gauge No. 214		
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
7 PVC	10 Asbestos-cement		
11 Other (specify)			
12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
7 Torch cut	10 Other (specify)		
SCREEN-PERFORATED INTERVALS:	From 50 ft. to xxx 70 ft., From	ft. to ft.	
GRAVEL PACK INTERVALS:	From 27 ft. to 32 ft., From	ft. to ft.	
	From 39 ft. to 70 ft., From	ft. to ft.	

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other Bentonite Holeplug
Grout Intervals:	From 0 ft. to 27 ft., From	ft. to 32 ft., From	ft. to 39 ft.	
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? Northeast			13 Insecticide storage	House
			How many feet? 50	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil, Clay			
3	6	Sand and Gravel			
6	13	Clay, Brown			
13	24	Sand and Gravel			
24	26.5	Clay			
26.5	33	Sand and gravel, very coarse			
33	39	Clay			
39	60	Sand and gravel			
60	63	Clay			
63	70	Sand and gravel, medium to coarse			
70		Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-25-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 7-26-93 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>
--

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.