


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction ne 1/4 ne 1/4 ne 1/4	Section number 19	Township number T 19 S	Range number R 13W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: Great Bend, Ks.			3. Owner of well: George Miller R.R. or street: Box 547 City, state, zip code: Great Bend, Ks. 67530			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole dia. 8 in. Completion date 4-8-78 Well depth 62 ft.	
Top Soil-Clay			0	15	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Sand-Gravel			15	30	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Clay			30	37	9. Casing: Material ☐ Height: Above ☒ Below ☒ Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight 2.8 lbs./ft. Dia. 5 in. to 62 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. Sch 40	
Sand-Gravel			37	62	10. Screen: Manufacturer's name Jetstream Type pvc Dia. 5" Slot/gauze 1/32" Length 20' Set between 42 ft. and 62 ft. ft. and ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/8-3/4"	
					11. Static water level: ☐ mo./day/yr. 14 ft. below land surface Date 4-8-78	
					12. Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 50 g.p.m.	
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐	
					14. Well head completion: ☐ Pitless adapter 12 inches above grade	
					15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: ft. 60 Direction nw Type sewer Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
			(Use a second sheet if needed)			
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Kellys Waterwell Ser 186 Business name R2 License No. Great Bend, Ks. Address Great Bend, Ks. Signed Kelly Price Date 9-22-79 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5