


WATER WELL RECORD Form WWC-5 kSA 82a-1212

1 LOCATION OF WATER WELL		Fraction	Near Center of		Section Number	Township Number	Range Number
County: Barton		1/4	1/4	NE 1/4	27	T 19 S	R 13 EW
Distance and direction from nearest town or city? 3/4 mile east of Great Bend, KS					Street address of well if located within city?		
2 WATER WELL OWNER: Buttons, Inc. RR#, St. Address, Box #: c/o Bill Button City, State, ZIP Code: Route 3, Great Bend, KS 67530 Board of Agriculture, Division of Water Resources Application Number: Not Available							
3 DEPTH OF COMPLETED WELL: 65 ft. Bore Hole Diameter: 24 in. to 65 ft. and in. to ft. Well Water to be used as: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 7 Lawn and garden only 10 Observation well Well's static water level: 11 1/2 ft. below land surface measured on 8 month 5 day 1980 year Pump Test Data: Well water was ft. after hours pumping gpm Est. Yield Not ck'd gpm: Well water was ft. after hours pumping gpm							
4 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile Casing Joints: Glued Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded XXX 7 Fiberglass Threaded Blank casing dia 16 in. to 25 ft. Dia in. to ft. Dia in. to ft. Casing height above land surface 12 in. weight 31.75 lbs./ft. Wall thickness or gauge No. 188 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) Screen or Perforation Openings Are: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) Doerr Bridge Slot Screen-Perforation Dia 16 in. to 65 ft. Dia in. to ft. Dia in. to ft. Screen-Perforated Intervals: From 25 ft. to 65 ft. From ft. to ft. Gravel Pack Intervals: From 10 ft. to 65 ft. From ft. to ft.							
5 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grouted Intervals: From 0 ft. to 10 ft. From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Cess pool 7 Sewage lagoon 10 Fuel storage 14 Abandoned water well 2 Sewer lines 5 Seepage pit 8 Feed yard 11 Fertilizer storage 15 Oil well/Gas well 3 Lateral lines 6 Pit privy 9 Livestock pens 12 Insecticide storage 16 Other (specify below) 13 Watertight sewer lines Direction from well Northwest How many feet 400 ? Water Well Disinfected? Yes No XX Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, date sample was submitted month day year Pump Installed? Yes 2/25 X No If Yes: Pump Manufacturer's name Peerless Pump Co. Model No. 12LB-2 HP 60 Volts 460 Depth of Pump Intake 60 ft. Pumps Capacity rated at 825 gal./min. Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other							
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 8 month 5 day 1981 year and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on 2 month 26 day 1981 year under the business name of Clarke Well & Eq., Inc. by (signature)							
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		0	3	Topsoil	57	64	Med.-coarse sand & gravel with clay streaks
		3	10	Sandy brown clay			
		10	36	Med-coarse sand & gravel	64	65	White & brown clay
		36-40	40	V.fine sand & gravel w/ some Med-coarse			
		40	44	Fine sand & gravel w/some clay streaks			
		44	47	Tan clay			
		47	52	Fine sand & gravel			
		52	55	Fine-med sand & gravel			
ELEVATION: Unknown		55	57	Med-coarse sand & gravel			
Depth(s) Groundwater Encountered 1. 11 1/2 ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)							
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.							