

WATER WELL RECORD		PUMP WELLS	RCA USE ONLY		
1 LOCATION OF WATER WELL:		Fraction NE County Barton 1905 Lakin st. ¼ SE ¼ 28	Township Number T 19 S Range Number R 13 E/W		
Distance and direction from nearest town or city street address of well if located within city? <u>1905 Lakin st. in city of Great Bend, Ks.</u>					
2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP Code :		Community Theatre Box 61 Great Bend, Ks. 67530 Board of Agriculture, Division of Water Resources Application Number: 585			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL . . . 80 . . . ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL . . . 16 . . . ft. below land surface measured on mo/day/yr . . 11-5-91 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gal/gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter . . 10 . . . in. to . . 80 . . . ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well . . air-conditioning Was a chemical/bacteriological sample submitted to Department? Yes . . . No . . X; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes hth No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued . . X . . Clamped			
Blank casing diameter . . 5 . . . in. to . . 5 . . . to . . 55 . . . ft., Dia in. to ft., Dia in. to ft. Casing height above land surface in., weight lbs./ft. Wall thickness or gauge No.					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
SCREEN OR PERFORATION OPENINGS ARE:		8 Saw cut 11 None (open hole)			
GRAVEL PACK INTERVALS:		From . . . 55 . . . ft. to . . 80 . . . ft., From ft. to ft. FROM ft. to ft., FROM ft. to ft.			
6 GROUT MATERIAL:		4 Other . . . hole plug			
Grout Intervals: From . . 4 . . . ft. to . . 20 . . . ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
Direction from well?		How many feet? 25			
LITHOLOGIC LOG		PLUGGING INTERVALS			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Tops oil			
3	7	Brown clay			
7	31	Sand and gravel			
31	41	Yellow brown clay			
41	58	Blue gray clay			
58	78	Sand and gravel clean loose			
78	89	Sand and gravel with clay			
this well had a Merrill pitless adaptor 5' bury put on it.					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) . . . 11-15-91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. . . 134 This Water Well Record was completed on (mo/day/yr) . . . 12-5-91 under the business name of Rosencrantz-Bemis by (signature) Fredia Redson					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY AND PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					