


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction NW 1/4 NW 1/4 NW 1/4	Section number 29	Township number T 19 S	Range number R 13 E/W
2. Distance and direction from nearest town or city: at 2325 Lincoln St. in Great Bend, Ks. Street address of well location if in city:				3. Owner of well: Don Scholler R.R. or street: 2325 Lincoln City, state, zip code: Great Bend, Kansas 67530		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 11 in. Completion date 9-6-79 Well depth 70 ft.		
				7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other		
top soil		0	3	9. Casing: Material PVC Height: Above or below Threaded ☐ Welded ☒ Surface 18 in. RMP PVC ☒ Weight 200 lbs./ft. Dia. 5 1/2 in. to 70 ft. depth Wall Thickness: inches or Dia. 5 in. to 70 ft. depth gauge No. 258		
clay		3	8	10. Screen: Manufacturer's name certain teed Type 1/16 Dia. 5 1/2 Slot/gauze 1/16 Length 20 Set between 50 ft. and 70 ft. ft. and 70 ft.		
gravel		8	28	Gravel pack? ☒ Size range of material 3/4-3/8-1/2		
hard clay		28	38	11. Static water level: 17 ft. below land surface Date 9-6-79 mo./day/yr.		
sand clay mixed		38	42	12. Pumping level below land surfaces: 17 ft. after 1 hrs. pumping 100 g.p.m. ft. after 1 hrs. pumping 100 g.p.m. Estimated maximum yield 300 g.p.m.		
good clean sand gravel		42	70	13. Water sample submitted: 9-6-79 mo./day/yr. ☒ Yes ☐ No		
clay		70		14. Well head completion: ☒ Pitless adapter 10 inches above grade		
				15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 6 ft. to 10 ft.		
				16. Nearest source of possible contamination: 60 ft. Direction south Type sewer line Well disinfected upon completion? ☐ Yes ☐ No		
				17. Pump: ☐ Not installed Manufacturer's name Red Jacket Model number FC HP 2 Volts 230 Length of drop pipe 42 ft. capacity 50 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Box 713 Great Bend, KS Signed Fredrick Rosencrantz Date 9/17/79 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5