


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 NE 1/4 SE 1/4	Section number 30	Township number T 19 S R 13 E	Range number 13 E	
2. Distance and direction from nearest town or city: Street address of well location if in city: 3701-22 Great Bend, KS			3. Owner of well: M. A. Snyder R.R. or street: 3701-22 City, state, zip code: Great Bend, KS				
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. 8 in. Completion date 4-12-76 Well depth 71 ft.			
5. Type and color of material		From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
Top Soil - Clay		0	12	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other			
Sand - Gravel		12	30	9. Casing: Material ☐ Height: ☒ Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 5 in. to 71 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. SC 40			
Clay		30	45	10. Screen: Manufacturer's name ANPI Type PVC Dia. 5-11 Slot/gauze 1/8 Length 20' Set between 51 ft. and 71 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/8-3/4"			
Sand - Gravel		45	71	11. Static water level: ☐ mo./day/yr. 14 ft. below land surface Date 4-15-76			
				12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 100 g.p.m.			
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date			
				14. Well head completion: ☐ Pitless adapter 12 inches above grade			
				15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.			
				16. Nearest source of possible contamination: sewer ft. 60 Direction E Type ☐ Well disinfected upon completion? ☒ Yes ☐ No			
				17. Pump: ☐ Not installed Manufacturer's name Grundfos Model number UTM HP 2 Volts 230 Length of drop pipe 40 ft. capacity 45 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
		(Use a second sheet if needed)					
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Kelly's Water Well Serv. Business name R2 Great Bend, KS License No. 186 Address Great Bend, KS Signed Kelly Price Date 4-20-76 Authorized representative			
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5