


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction SE 1/4 NW 1/4 SE 1/4	Section number 31	Township number T 19 S	Range number R 13 E
2. Distance and direction from nearest town or city: 1 mi. South of Great Bend, KS Street address of well location if in city:				3. Owner of well: Cecil Appel R.R. or street: P. O. Box 1063 City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 9 in. Completion date 5-17-76 Well depth 60 ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil & fill		0	4	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight XXXX lbs./ft. 1.5 Dia. 5 in. to 60 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. XXXX 200#		
Brown clay		4	8	10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" ☒ Slotted gauze 1/8 Length 10' Set between 50 ft. and 60 ft. ft. and ☐ ft.		
Sand & gravel		8	31	Gravel pack? Yes Size range of material 3/8-200		
Yellow & blue clay		31	44	11. Static water level: ☐ mo./day/yr. 10 ft. below land surface Date 5-17-76		
Sand & gravel		44	60	12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No ☐ Date ☐		
				14. Well head completion: ☐ Pitless adapter 12 inches above grade		
				15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft. NONE KNOWN		
				16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed Clarke Date 5-26-76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5