

1 LOCATION OF WATER WELL: County: Barton	Fraction NE 1/4 NW 1/4 NE 1/4	Section Number 33	Township Number T 19 S	Range Number R 9 E
--	---	-----------------------------	----------------------------------	------------------------------

Distance and direction from nearest town or city street address of well if located within city?

Taylor Food Mart 1615 10th St. Great Bend, Ks.

2 WATER WELL OWNER: EZ Serve	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: P.O. Box 922021	Application Number:
City, State, ZIP Code: Houston, TX. 77292-2021	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 15'6" ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. 8' ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 7.30 ft. below land surface measured on mo/day/yr 5-10-94 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 1/2" in. to 15'6" ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter 2.375 in. to 5' ft., Dia			Threaded X
Casing height above land surface Flush Mount in., weight			lbs./ft. Wall thickness or gauge No. SDR 13
TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement	SCH 40
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS: From 15' ft. to 5' ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From 15'6" ft. to 4' ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 4' ft. to 3' ft., From 3' ft. to 0' ft., From ft. to ft.				
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage
	2 Sewer lines	5 Cess pool	8 Sewage lagoon	12 Fertilizer storage
	3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage
Direction from well? Southeast				How many feet? 40'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	.50	Concrete			
.50	3.75	Dk brn -gray brn silty sandy clay, moist, no odor.			
3.75	9.50	Fine-med. grained sand, dry, loose, no odor, subrounded, poorly sorted.			
9.50	15'6"	Brn silty sand, wet, no odor, fine-coarse grained sand & gravel, subrounded..			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-10-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 539 This Water Well Record was completed on (mo/day/yr) 5-14-94 under the business name of JB Environmental Drilling by (signature) James Bicker
