

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		SE 1/4 NW 1/4 SE 1/4	28	T 19 S	R 13 E (W)
Distance and direction from nearest town or city street address of well if located within city? At 1421 Holland Street in Great Bend					
2 WATER WELL OWNER: St. Rose Catholic Church RR#, St. Address, Box # : 1421 Holland Street City, State, ZIP Code : Great Bend, KS 67530 Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 70 ft. ELEVATION: unknown			
		Depth(s) Groundwater Encountered 1 _____ ft. 2 _____ ft. 3 _____ ft.			
		WELL'S STATIC WATER LEVEL 18.80 ft. below land surface measured on mo/day/yr 8-5-04			
		Pump test data: Well water was not checked ft. after _____ hours pumping _____ gpm			
		Est. Yield unknown gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter 9 in. to 72 ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below) 2 Irrigation 4 Industrial (7) Domestic (lawn & garden) 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? Yes ☒ No _____			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile		CASING JOINTS: Glued ☒ Clamped	
(2) PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)		Welded _____	
		7 Fiberglass		Threaded _____	
Blank casing diameter 5 in. to 58 ft., Dia		in. to _____ ft., Dia		in. to _____ ft.	
Casing height above land surface 24 in., weight 2.36 lbs./ft.		Wall thickness or gauge No .214			
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		10 Asbestos-cement			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		11 Other (specify) _____			
		12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot (3) Mill slot 5 Gauzed wrapped		8 Saw cut 11 None (open hole)			
2 Louvered shutter 4 Key punched 6 Wire wrapped		9 Drilled holes			
		10 Other (specify) _____			
SCREEN-PERFORATED INTERVALS:		From 58 ft. to 68 ft., From _____ ft. to _____ ft.			
		From _____ ft. to _____ ft., From _____ ft. to _____ ft.			
GRAVEL PACK INTERVALS:		From 20 ft. to 43 ft., From _____ ft. to _____ ft.			
		From 45 ft. to 68 ft., From _____ ft. to _____ ft.			
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug					
Grout Intervals: From _____ ft. to _____ ft., From 0 ft. to 20 ft., From 43 ft. to 45 ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy		10 Livestock pens 14 Abandoned water well			
2 Sewer lines 5 Cess pool 8 Sewage lagoon		11 Fuel storage 15 Oil well/Gas well			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		12 Fertilizer storage 16 Other (specify below)			
		13 Insecticide storage None known			
Direction from well? _____ How many feet? _____					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil			
3	7	Clay, brown			
7	31	Sand and gravel, fine to coarse			
31	49	Clay, tan			
49	58	Clay, tan with sand streaks			
58	70	Sand and gravel, fine to coarse			
70	72	Clay, tan			
RECEIVED					
AUG 26 2004					
BUREAU OF WATER					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-5-04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 8-17-04 under the business name of Clarke Well & Equipment, Inc. by (signature) _____					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.					