

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Barton	NC 1/4 SE 1/4 SE 1/4	20	T 19 S	R 13 E W

Distance and direction from nearest town or city street address of well if located within city?

Behind Jefferson Elementary School at 2716 24th Street

2 WATER WELL OWNER: Unified School District #428	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : 201 Patton Rd.	Application Number:
City, State, ZIP Code : Great Bend, KS 67530	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 62 ft. ELEVATION: unknown
--	---

Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft.

WELL'S STATIC WATER LEVEL 13.62 ft. below land surface measured on mo/day/yr 6-23-05

Pump test data: Well water was not checked ft. after hours pumping gpm

Est. Yield unknown gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter 10 in. to 63.5 ft., and in. to ft.

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below)

2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes ☒ No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ☒ Clamped ☒
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below) Welded
2 PVC	4 ABS	7 Fiberglass	Threaded
Blank casing diameter 5 in. to 32 ft., Dia	5 in. to 50 ft., Dia	in. to ft.	
Casing height above land surface 24 in., weight	2.36 lbs./ft.	Wall thickness or gauge No .214	
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	7 PVC
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped	8 Saw cut
1 Continuous slot	3 Mill slot	6 Wire wrapped	11 None (open hole)
2 Louvered shutter	4 Key punched	7 Torch cut	9 Drilled holes
SCREEN-PERFORATED INTERVALS:		10 Other (specify)	
From 32 ft. to 42 ft., From	ft. to ft.		
From 50 ft. to 60 ft., From	ft. to ft.		
GRAVEL PACK INTERVALS:	From 20 ft. to 63 ft., From	ft. to ft.	
From	ft. to ft.		

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other	Bentonite Holeplug
Grout Intervals: From ft. to ft., From ft. to ft., From 0 ft. to 20 ft.					
What is the nearest source of possible contamination:					
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well	
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well	
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)	
			13 Insecticide storage	None known	
Direction from well?			How many feet?		

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil			
3	7	Clay, dark gray, soft			
7	31	Sand and gravel, coarse to fine, loose and clean with large rock			
31	42	Sand and gravel, coarse to fine, loose and clean			
42	50	Clay, tannish brown, hard			
50	63	Sand and gravel, coarse to fine			
63	63.5	Clay, tan, hard			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-23-05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 6-24-05 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>	
---	--