

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		NW 1/4 SW 1/4 SE 1/4	16	T 19 S	R 13 E (W)
Distance and direction from nearest town or city street address of well if located within city? 62 Karen Street in Great Bend			Global Positioning Systems (decimal degrees, min. of 4 digits)		
			Latitude: 38.393457		
			Longitude: -98.763281		
2 WATER WELL OWNER: Keith Patterson			Elevation: Unknown		
RR#, St. Address, Box # : 2218 32nd St.			Datum: NAD83		
City, State, ZIP Code : Great Bend, KS 67530			Data Collection Method: WAAS GPS Unit		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 60 ft.			
		Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft.			
		WELL'S STATIC WATER LEVEL 13.35 ft. below land surface measured on mo/day/yr 09-25-08			
		Pump test data: Well water was Not checked ft. after _____ hours pumping _____ gpm			
		Est. Yield Unknown gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		(1) Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr _____			
		Sample was submitted _____ Water well disinfected? Yes ☒ No _____			
5 TYPE OF CASING USED:					
1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) _____ (2) PVC 4 ABS 7 Fiberglass _____					
Blank casing diameter 5 in. to 48 ft., Diameter _____ in. to _____ ft., Diameter _____ in. to _____ ft.					
Casing height above land surface 24 in., weight 2.36 lbs./ft. Wall thickness or gauge No. 214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless Steel 5 Fiberglass (7) PVC 9 ABS 11 Other (Specify) _____ 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot (3) Mill slot 5 Gauzed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw Cut 10 Other (Specify) _____					
SCREEN-PERFORATED INTERVALS: From 48 ft. to 58 ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From 24 ft. to 60 ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat Cement 2 Cement grout (3) Bentonite 4 Other _____					
Grout Intervals: From _____ ft. to _____ ft., From 4 ft. to 24 ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage (16) Other (specify below) 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well None known 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer Storage 15 Oil well/gas well					
Direction from well? _____ How many feet? _____					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil			
3	16	Clay, brown, soft, silty			
16	17	Clay, black, soft			
17	33	Sand and gravel, coarse to fine, loose, clean			
33	35	Clay, tan, hard			
35	41	Sand and gravel, medium to fine, loose, clean			
41	43	Clay, tan, hard			
43	60	Sand and gravel, medium to fine to coarse, with large rock, loose and clean			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:					
This water well was (1) constructed (2) reconstructed (3) plugged under my jurisdiction and was completed on (mo/day/year) 09-25-08 and this record is true to the best of my knowledge and belief.					
Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 10-02-08					
Under the business name of Clarke Well & Equipment, Inc. by (signature) _____					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.					