

1 LOCATION OF WATER WELL: County: Barton		Fraction 1/4 NW 1/4 NW 1/4 SW 1/4		Section Number 9		Township No. T 19 S		Range Number R 13 E ☐ W ☒																																																	
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 2 1/4 miles north of Great Bend				Global Positioning System (GPS) information: Latitude: 38.41254 (in decimal degrees) Longitude: -98.774432 (in decimal degrees) Elevation: Unknown Datum: ☐ WGS 84, ☐ NAD 83, ☒ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																					
2 WATER WELL OWNER: City of Hoisington RR#, Street Address, Box #: P.O. Box 418 City, State, ZIP Code: Hoisington, KS 67544																																																									
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="display: inline-table; border-collapse: collapse;"><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr><tr><td style="width: 20px; height: 20px; text-align: center;">X</td><td style="width: 20px; height: 20px;"></td></tr><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr></table> E S -----1 mile-----				X				4 DEPTH OF COMPLETED WELL 130.4 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 18.65 ft. below land surface measured on mo/day/yr 10/22/09 Pump test data: Well water was Not checked ft. after _____ hours pumping _____ gpm EST. YIELD Unknown gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter _____ in. to _____ ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☒ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																	
X																																																									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 95 ft., Diameter _____ in. to _____ ft., Diameter _____ in. to _____ ft. Casing height above land surface 30 in., Weight 19.75 lbs./ft., Wall thickness or gauge No. .616 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☒ Stainless Steel ☐ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☒ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 95 ft. to 128 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 51 ft. to 129 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																									
6 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☐ Bentonite ☒ Other 50% Bentonite Holeplug / 50% Sand Grout Intervals: From 3 ft. to 24 ft., From _____ ft. to _____ ft., From 24 ft. to 51 ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None known Direction from well _____ Distance from well _____																																																									
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0</td><td>22</td><td>Clay, dark brown</td><td>120</td><td>128</td><td>Sand and gravel, fine, medium, some coarse</td></tr><tr><td>22</td><td>41</td><td>Sand and gravel, fine, medium, some coarse</td><td>128</td><td>129</td><td>Clay, red and gray</td></tr><tr><td>41</td><td>49</td><td>Clay, green and gray</td><td></td><td></td><td></td></tr><tr><td>49</td><td>61</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr><tr><td>61</td><td>94</td><td>Clay, tan, hard</td><td></td><td></td><td></td></tr><tr><td>94</td><td>107</td><td>Sand and gravel, fine, medium, some coarse</td><td></td><td></td><td></td></tr><tr><td>107</td><td>120</td><td>Clay, tan, with gravel</td><td></td><td></td><td></td></tr></tbody></table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	22	Clay, dark brown	120	128	Sand and gravel, fine, medium, some coarse	22	41	Sand and gravel, fine, medium, some coarse	128	129	Clay, red and gray	41	49	Clay, green and gray				49	61	Sand and gravel, fine, medium				61	94	Clay, tan, hard				94	107	Sand and gravel, fine, medium, some coarse				107	120	Clay, tan, with gravel			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																				
0	22	Clay, dark brown	120	128	Sand and gravel, fine, medium, some coarse																																																				
22	41	Sand and gravel, fine, medium, some coarse	128	129	Clay, red and gray																																																				
41	49	Clay, green and gray																																																							
49	61	Sand and gravel, fine, medium																																																							
61	94	Clay, tan, hard																																																							
94	107	Sand and gravel, fine, medium, some coarse																																																							
107	120	Clay, tan, with gravel																																																							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☐ constructed, ☒ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 10/22/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 10/28/09 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>[Signature]</i>																																																									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																									