

WATER WELL PLUGGING RECORD Form WWC-5P

KSA 82a-1212

ID NO.

20079003

1 LOCATION OF WATER WELL:County: **Barton**

Fraction

1/4 SE 1/4 SE 1/4 SE 1/4

Section Number

8

Township Number

T 19 S

Range Number

13

☐ E☒ W

Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐

Approximately 1 3/4 miles north of Great Bend

Global Positioning Systems (GPS) information:Latitude: **38.406623**


(in decimal degrees)

Longitude: **-98.776466**

(in decimal degrees)

Elevation: **unknown**

Datum:

☐ WGS84,☒ NAD83,☐ NAD27**Collection Method:**☒ GPS unit (Make/Model: **WAAS**)☐ Digital Map/Photo,☐ Topographic Map,☐ Land SurveyEst. Accuracy: ☐ < 3 m,☒ 3-5 m,☐ 5-15 m,☐ > 15 m**3 MARK WELL'S LOCATION WITH AN "X" IN SECTION BOX:****4 DEPTH OF WELL** 107.6 ft.WELL'S STATIC WATER LEVEL 17.1 ft

WELL WAS USED AS:

☐ Domestic☒ Public Water Supply☐ Dewatering☐ Irrigation☐ Oil Field Water Supply☐ Monitoring☐ Feedlot☐ Domestic (Lawn & Garden)☐ Injection Well☐ Industrial☐ Air Conditioning☐ Other _____Was a chemical/bacteriological sample submitted to Department? Yes ☐ No ☒**5 TYPE OF BLANK CASING USED:**☒ Steel☐ RMP (SR)☐ Wrought☐ Fiberglass☐ Other (Specify below) _____☐ PVC☐ ABS☐ Asbestos-Cement☐ Concrete TileBlank casing diameter 12 in. Was casing pulled? Yes ☐ No ☒ If yes, how much _____Casing height above or below land surface. _____ in.
In Well House (See attached)**6 GROUT PLUG MATERIAL:**☐ Neat cement☒ Cement grout☒ Bentonite☐ Other _____Grout Plug Intervals: From 0 ft. to 2.5 ft., From 2.5 ft. to 17.1 ft., From _____ to _____ ft.

What is the nearest source of possible contamination:

☐ Septic tank☐ Seepage pit☐ Fuel Storage☒ Other (specify below)☐ Sewer lines☐ Pit privy☐ Fertilizer storageNone known☐ Watertight sewer lines☐ Sewage lagoon☐ Insecticide storage☐ Lateral lines☐ Feedyard☐ Abandoned water well

Direction from well? _____

☐ Cess pool☐ Livestock pens☐ Oil well/Gas well

How many feet? _____

FROM	TO	PLUGGING MATERIALS	FROM	TO	PLUGGING MATERIALS
107.6	17.1	Chlorinated sand and gravel			
17.1	2.5	Bentonite Chips			
2.5	0	Concrete Grout			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was plugged under my jurisdiction and was completed on (mo/day/year) 3/2/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185. This Water Well Record was completed on (mo/day/year) 3/5/10 under the business name of Clarke Well & Equipment, Inc. by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ballpoint pen. Please press firmly and print clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Ste. 420, Topeka, Kansas 66612-1367. Telephone: 785/296-5524. Send one to Water Well Owner and retain one for your records. Visit us at <http://www.kdheks.gov/waterwell/l~ndex.html>.

Check one:

☐ White Copy☐ Blue Copy☐ Pink Copy

Return-path: <rharper@kdheks.gov>
Envelope-to: clarkewell@opiwireless.com
From: Richard Harper <rharper@kdheks.gov>
To: Clarke Well & Equipment <clarkewell@opiwireless.com>
Date: Mon, 1 Mar 2010 12:57:54 -0600
Subject: RE: Well Plugging
References: <20100301160432.DFCB812827B@smtp1.ruraltel.net>
In-Reply-To: <20100301160432.DFCB812827B@smtp1.ruraltel.net>
Accept-Language: en-US
acceptlanguage: en-US

Brent,

That would be acceptable.

Thanks Richard

-----Original Message-----

From: Clarke Well & Equipment [<mailto:clarkewell@opiwireless.com>]
Sent: Monday, March 01, 2010 10:04 AM
To: Richard Harper
Subject: Well Plugging

Richard,

We are getting ready to plug a well for All-Seasons Mobile Home Park in Great Bend. It is a PWS well inside a well house with a concrete well block approximately 2 feet above the well house floor. Is it acceptable to grout the well from static water level up to the top of the well block and not remove any casing? This well has concrete grout around the well casing in addition to the concrete well block. We are planning on using a bentonite grout from SWL to ground level and then place concrete grout from ground level to the top of the well block.

Thanks,

Brent

Brent Clarke
Clarke Well & Equipment
8822 3rd St
Great Bend, KS 67530
(620) 793-8493
clarkewell@opiwireless.com