

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number			
County: Barton		NE 1/4 SW 1/4 NE 1/4		28		T 19 S		R 14 E/W			
Distance and direction from nearest town or city street address of well if located within city?											
Approximately 3 1/4 miles west of Great Bend											
2 WATER WELL OWNER:		Phillip J. Martin									
RR#, St. Address, Box # :		424 SW 20th Ave.									
City, State, ZIP Code :		Great Bend, KS 67530									
		Board of Agriculture, Division of Water Resources Application Number: 13,321									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:				4 DEPTH OF COMPLETED WELL: 112 ft. ELEVATION: unknown							
				Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.							
				WELL'S STATIC WATER LEVEL 28 ft. below land surface measured on mo/day/yr 8-1-97							
				Pump test data: Well water was not ch'd ft. after hours pumping gpm							
				Est. Yield unknown gpm: Well water was ft. after hours pumping gpm							
				Bore Hole Diameter 24 in. to 111 ft. and in. to ft.							
				WELL WATER TO BE USED AS:							
				5 Public water supply 8 Air conditioning 11 Injection well							
				1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)							
				2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well							
				Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted							
				Water Well Disinfected? Yes No ☒							
5 TYPE OF BLANK CASING USED:											
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped ☒											
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded ☒											
7 Fiberglass Threaded											
Blank casing diameter 16 in. to 47 ft. Dia. in. to ft. Dia. in. to ft.											
Casing height above land surface 12 in. weight 31.66 lbs./ft. Wall thickness or gauge No. 188											
TYPE OF SCREEN OR PERFORATION MATERIAL:											
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement											
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)											
12 None used (open hole)											
SCREEN OR PERFORATION OPENINGS ARE:											
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)											
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes											
7 Torch cut 10 Other (specify) Bridge Slot											
SCREEN-PERFORATED INTERVALS: From 47 ft. to 111 ft. From ft. to ft.											
From ft. to ft. From ft. to ft.											
GRAVEL PACK INTERVALS: From 20 ft. to 111 ft. From ft. to ft.											
From ft. to ft. From ft. to ft.											
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other											
Grout Intervals: From 0 ft. to 20 ft. From ft. to ft. From ft. to ft.											
What is the nearest source of possible contamination:											
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well											
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well											
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)											
13 Insecticide storage None known											
Direction from well? How many feet?											
FROM		TO		LITHOLOGIC LOG		FROM		TO		PLUGGING INTERVALS	
0		2		Topsoil							
2		8		Clay							
8		25		Sand and gravel, medium, coarse, very coarse							
25		35		Sand and gravel, medium, coarse							
35		51		Sand and gravel, fine, medium							
51		63		Clay, brown							
63		92		Sand and gravel, fine, medium							
92		95		Clay, brown							
95		106		Sand and gravel, fine, medium							
106		110		Sand and gravel with clay							
110		111		Clay							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-1-97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 8-22-97 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>											