

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Barton	Fraction NW 1/4 NE 1/4 SE 1/4	Section number 4	Township number T 19 S R 14 E W	Range number
2. Distance and direction from nearest town or city: 7 miles Northwest of Great Bend, KS Street address of well location if in city:			3. Owner of well: K. W. Kirkman R.R. or street: 1909 Lincoln City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile Sketch map:			6. Bore hole dia. 24 in. Completion date 6-26-78 Well depth 75 ft. Pump Set 7-3-78		
			7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☒ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
			8. Use: Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☒ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐		
5. Type and color of material			9. Casing: Material steel Height: Above or below surface 12 in. Threaded ☐ Welded ☒ RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 33 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 7 ga.		
			10. Screen: Manufacturer's name B-W. A. Brown C-Cook Double-slot Dia. 16" Slot gauze 1/8" Length B-32 C-10 Set between B 33 ft. and 65 ft. and C 65 ft. and 75 ft. Gravel pack? Yes Size range of material 3/8-200		
Top soil			From 0 To 3		
Brown clay			From 3 To 27		
Sand & gravel			From 27 To 45		
Sand & gravel & clay streak			From 45 To 53		
XXX Soft blue clay & sand streak			From 53 To 63		
Sand & gravel & clay streak at 69 to 70			From 63 To 74		
Dakota clay & sandstone			From 74 To 75		
			11. Static water level: _____ mo./day/yr. 23'6" ft. below land surface Date 6-28-78		
			12. Pumping level below land surfaces: Not Checked _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.		
			13. Water sample submitted: _____ mo./day/yr. Yes ☐ No ☒ Date _____		
			14. Well head completion: _____ Pitless adapter 12 Inches above grade		
			15. Well grouted? X Yes With: X Neat cement _____ Bentonite _____ Concrete _____ Depth: From 0 ft. to 10 ft.		
			16. Nearest source of possible contamination: FIELD ft. _____ Direction _____ Type _____ Well disinfected upon completion? _____ Yes ☒ No ☐		
			17. Pump: _____ Not installed Manufacturer's name Peerless Pump Co. Model number 12MB-2 HP 25 Volts 460 Length of drop pipe 70 ft. capacity 900 g.p.m. Type: _____ Submersible _____ X Turbine _____ Jet _____ Reciprocating _____ Centrifugal _____ Other _____		
(Use a second sheet if needed)					
18. Elevation: 1883 Topography: _____ Hill _____ Slope _____ Upland _____ Valley _____		19. Remarks: 7330 19 14 4 DAB		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc 185 Business name _____ License No. _____ Address Great Bend, KS 67530 Signed _____ Date 7-11-78 Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5