


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction CSE 1/4 1/4 1/4	Section number 5	Township number T 19 S R 14 NW	Range number
2. Distance and direction from nearest town or city: 114 W			3. Owner of well: Maurice Nordman			
Street address of well location if in city: 4612 E, KS			R.R. or street: Rt. 612 E, KS			
City, state, zip code:						
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 8 in. Completion date 5-7-77 Well depth 54 ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From To		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top Soil - Clay		7 14		9. Casing: Material PVC Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight 15 lbs./ft. Dia. 5 in. to 24 ft. depth Wall Thickness: inches or Dia. 5 in. to 24 ft. depth gage No. SC440		
Sand		14 25		10. Screen: Manufacturer's name MPI Type PVC Dia. 5" Slot/gauze 1/16" Length 15' Set between 39 ft. and 54 ft. ft. and 54 ft.		
Clay		25 36		Gravel pack? ☒ Size range of material 1/8-3/4"		
Sand - Gravel		36 54		11. Static water level: 12 ft. below land surface Date 5-7-77 mo./day/yr.		
				12. Pumping level below land surfaces: ft. after 30 hrs. pumping 30 g.p.m. ft. after 30 hrs. pumping 30 g.p.m. Estimated maximum yield 30 g.p.m.		
				13. Water sample submitted: Yes ☒ No ☐ Date		
				14. Well head completion: Pitless adapter 12 inches above grade		
				15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 16 ft.		
				16. Nearest source of possible contamination: Septic ft. 60 Direction S Type TANK Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 186 Kelly S. Blayden Business name K2 Great Bend, KS License No. Address Kelly Vance Date 8-20-77 Signed Kelly Vance Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5