


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction C 1/4 SE 1/4 SE 1/4	Section number 19	Township number T 19 S	Range number R 14 E
2. Distance and direction from nearest town or city: 6 miles West of Great Bend, KS Street address of well location if in city:			3. Owner of well: Mark Calcara R.R. or street: Route 4 City, state, zip code: Great Bend, KS 67530			
4. Locate with "X" in section below: 			Sketch map:		6. Bore hole dia. 9 in. Completion date 9-28-78 Well depth 55 ft. Pump Set 10-16-78	
5. Type and color of material			From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Top soil			0	3	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other	
Brown clay			3	40	9. Casing: Material Styrene Height: ☒ Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 in. to 45 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 200	
Sand & gravel			40	54	10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" ☒ Slot gauze 1/8" Length 10' Set between 45 ft. and 55 ft. ☐ ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200	
Brown clay			54	55	11. Static water level: ☐ mo./day/yr. 35 ft. below land surface Date 9-28-78	
BP 2-57					12. Pumping level below land surfaces: Not Checked ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐	
					14. Well head completion: ☐ Pitless adapter ☐ 12 Inches above grade	
					15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Berkeley Pump CO Model number 4BM-12 HP 1 1/2 Volts 230 Length of drop pipe 46 1/2 ft. capacity 15 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name ☐ License No. ☐ Address Great Bend, KS 67530 Signed [Signature] Date 10-17-78 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5