

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Barton	Fraction 1/4 SE 1/4 SE 1/4	Section number 27	Township number T 19 S	Range number R 14 E (W)
2. Distance and direction from nearest town or city: 1 1/2 mi. West of Great Bend, KS Street address of well location if in city:			3. Owner of well: Mrs. Earl Geil R.R. or street: Route 1 City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 6. Bore hole dia. 6 in. Completion date 3-9-76 Well depth 45 ft. 7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material PVC Height Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight 5 lbs./ft. Dia. 2 in. to 38 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 091		
5. Type and color of material			From	To	
Top soil			0	3	10. Screen: Manufacturer's name Peerless Plastics, Inc. Type PVC Dia. 2" ☒ Slot gauze 1/8 Length 7' Set between 38 ft. and 45 ft. Gravel pack? Yes Size range of material 3/8-200
Brown clay			3	14	11. Static water level: 15 1/2 ft. below land surface Date 3-6-76
Sand & gravel			14	31	12. Pumping level below land surfaces: N/C ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
Blue & xxx yellow clay			31	37	13. Water sample submitted: ____ mo./day/yr. ☐ Yes ☒ No Date ____
Sand & gravel			37	45	14. Well head completion: 12 Inches above grade ☐ Pitless adapter
					15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
					NONE KNOWN 16. Nearest source of possible contamination: ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: ☐ Not installed Manufacturer's name Berkeley Pump Co. Model number D-5 HP 1/2 Volts ____ Length of drop pipe 21 ft. capacity 6 g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☒ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed D. W. Clarke Date 3-28-76 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5