


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction SW 1/4 NW 1/4 NW 1/4	Section number 36	Township number T 19 S	Range number R 14 E
2. Distance and direction from nearest town or city: 1 mi. West of Great Bend, KS Street address of well location if in city:				3. Owner of well: David Essmiller R.R. or street: Route 1 City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 24 in. Completion date 10-21-75 Well depth 116 ft.		
				7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐		
				9. Casing: Material Steel Height Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to ☐ ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 7 ga.		
5. Type and color of material		From To		10. Screen: Manufacturer's name SEE RECORD BELOW Type 1 1/8 Dia. 16" Slot gauge 1 1/8 Length 65' Set between ☐ ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200		
Top soil		0 4		11. Static water level: ☐ mo./day/yr. 10 ft. below land surface Date 10-21-75		
Sand & gravel		4 20		12. Pumping level below land surfaces: N/C ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
Sand, gravel & clay streaks		20 30		13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No Date ☐		
Sand & gravel		30 40		14. Well head completion: Pitless adapter 12 inches above grade		
Brown clay		40 45		15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
Sand & gravel		45 65		16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
Brown clay & gravel streaks		65 78		17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Sand & gravel		78 89				
Brown clay		89 94				
Sand & gravel		94 115				
Blue clay		115 116				
CASING & SCREEN RECORD						
Plain casing		0 36				
Johnson Division screen -- .125 Irrigator		36 41				
Plain casing		41 46				
Doerr screen -- Double-slot		46 66				
Plain casing		66 76				
Doerr screen -- Double-slot		76 116				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Great Bend, KS License No. 10-21-75 Address 1899 Signed D.W. Clarke Authorized representative		