


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Barton	Fraction SE 1/4 SE 1/4 NE 1/4	Section number 36	Township number T 19 S R 14 E	Range number 14
2. Distance and direction from nearest town or city: 1/2 mile south of Great Bend, KS Street address of well location if in city:			3. Owner of well: Mrs. Herman Scheck R.R. or street: 2017 No. "C" City, state, zip code: Arkansas City, KS 67005		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. 9 in. Completion date 2-22-78 Well depth 60 ft.
Top Soil			0	3	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
Brown Clay and Sand			3	7	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ ☐ Lawn ☐ Oil field water ☐ Other
Sand And Gravel			7	31	9. Casing: Material Styrene Weight: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 in. to 50 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 200#
Yellow and Blue Clay			31	42	10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" Slot gauge 1/8 Length 10' Set between 50 ft. and 60 ft. Gravel pack? yes Size range of material 3/8-200
Sand and Gravel			42	60	11. Static water level: 14 ft. below land surface Date 2/22/78 mo./day/yr.
B9 ≥ 60 fpu					12. Pumping level below land surfaces: NC ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
					13. Water sample submitted: mo./day/yr. Yes ☒ No ☐ Date
					14. Well head completion: Pitless adapter 12 Inches above grade
					15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: ft. Direction Type Field Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: ☐ Not installed Manufacturer's name Berkeley Model number 4AM-11 HP 1/2 Volts 230 Length of drop pipe 30 ft. capacity 10 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Equip., Inc. 185 Business name Great Bend, KS 67530 Address Great Bend, KS 67530 Signed D. W. Clarke Date 3/28/78 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					