

1 LOCATION OF WATER WELL:		Fraction	SE 1/4 SE 1/4 SE 1/4	Section Number	36	Township Number	T 19 S	Range Number	R 14 E/W
Distance and direction from nearest town or city street address of well if located within city?									
Located on South Patton Road/Hwy 56 - Address n/a									
2 WATER WELL OWNER:		Terry Lewis - c/o Lewis Jewelers							
RR#, St. Address, Box # :		1214 Main - @ Zarah Mall							
City, State, ZIP Code :		Great Bend, KS 67530							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 70 ft. ELEVATION: unknown							
		Depth(s) Groundwater Encountered 1. 14 ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL 14 ft. below land surface measured on mo/day/yr 2/23/87							
		Pump test data: Well water was not ck'd. ft. after hours pumping gpm							
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter 9 in. to 68 ft., and in. to ft.							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped							
1 Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded							
2 PVC 4 ABS		7 Fiberglass Threaded							
Blank casing diameter 5 in. to 48 ft., Dia		Casing height above land surface 24 in., weight 2.277 lbs./ft. Wall thickness or gauge No. .214							
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement							
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)		2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)							
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes		2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS:		From 48 ft. to 68 ft., From ft. to ft.							
GRAVEL PACK INTERVALS:		From 40 ft. to 68 ft., From ft. to ft.							
annular fill From 10 ft. to 34 ft., From ft. to ft.									
6 GROUT MATERIAL:		a) 1 Neat cement 2 Cement grout b) 3 Bentonite 4 Other							
Grout intervals: From a) 3 ft. to 10 ft., From b) 34 ft. to 40 ft., From ft. to ft.									
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well							
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well		2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)							
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage		Direction from well? south How many feet? 50							
FROM	TO	LITHOLOGIC LOG		FROM	TO	LITHOLOGIC LOG			
0	8	Topsoil & brown clay							
8	34	Sand & gravel, fine to medium to coarse, w/streak of soft black clay @ 24'							
34	46	Yellow-tan & gray clay							
46	68	Sand & gravel, med. to fine, clean and loose							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 2/23/87 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 3/13/87 under the business name of Clarke Well & Equipment, Inc. by (signature)									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Office of Oil Field and Environmental Geology, Regulation and Permitting Section, Topeka, Kansas 66620-7500, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.									