

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		SE 1/4 SW 1/4 SE 1/4	34	T 19 S	R 14 E/W
Distance and direction from nearest town or city street address of well if located within city?					
North of hangar at Great Bend Airport					
2 WATER WELL OWNER:		City of Great Bend			
RR#, St. Address, Box # :		1209 Williams			
City, State, ZIP Code :		Great Bend, KS 67530			
		Board of Agriculture, Division of Water Resources			
		Application Number: 36,205			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 119 ft. ELEVATION: Unknown			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 14 ft. below land surface measured on mo/day/yr 12/28/98			
		Pump test data: Well water was not ch'd. ft. after hours pumping gpm			
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 30 in. to 119 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes ☒ No ☐ If yes, mo/day/yr sample was submitted 2/16/98 & 7/27/98			
		Water Well Disinfected? Yes ☒ No ☐			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued ☐ Clamped ☐			
1 Steel 3 RMP (SR)		Welded ☒			
2 PVC 4 ABS		Threaded ☐			
Blank casing diameter 10 3/4 in. to 102 ft., Dia		in. to ft., Dia			
Casing height above land surface 12 in., weight 40.47 lbs./ft. Wall thickness or gauge No. .365					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 102 ft. to 118 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 83 ft. to 119 ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug					
Grout Intervals: From 0 ft. to 5 ft., From 5 ft. to 77 ft., From 77 ft. to 83 ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage None known					
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PERFORATION INTERVALS
0	3	Topsoil	106	118	Sand and gravel, fine, medium
3	6	Clay, silty	118	119	Clay, dark gray
6	17	Sand and gravel			
17	27	Sand and gravel, medium, coarse, very coarse			
27	32	Clay, tan			
32	42	Sand and gravel, fine, medium			
42	46	Clay, brown			
46	49	Clay with sand and gravel			
49	74	Sand and gravel, fine, medium			
74	79	Clay, brown			
79	85	Sand and gravel, fine, medium			
85	90	Sand and gravel, fine			
90	105	Sand and gravel, fine, medium			
105	106	Clay, gray			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12/28/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 1/5/99 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					