

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Barton		SE ¼ SW ¼ SE ¼		34		T 19 S		R 14 E/W	
Distance and direction from nearest town or city street address of well if located within city?									
North of hangar at Great Bend Airport									
2 WATER WELL OWNER:		City of Great Bend							
RR#, St. Address, Box # :		1209 Williams							
City, State, ZIP Code :		Great Bend, KS 67530							
		Board of Agriculture, Division of Water Resources Application Number: 36,205							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 109 ft. ELEVATION: unknown							
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL . . . 15 . . . ft. below land surface measured on mo/day/yr . 12/30/98							
		Pump test data: Well water was not ch'd. ft. after hours pumping gpm							
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter . . . 30 . . . in. to ft., and in. to ft.							
		WELL WATER TO BE USED AS:							
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well							
		Was a chemical/bacteriological sample submitted to Department? Yes . . . X . . . No; If yes, mo/day/yr sample was submitted 2/16/98 & 7/27/98							
		Water Well Disinfected? Yes X No							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded . . . X . . . 2 PVC 4 ABS 7 Fiberglass Threaded							
Blank casing diameter . . . 10 3/4 . . . in. to . . . 92 . . . ft., Dia in. to ft., Dia in. to ft.									
Casing height above land surface . . . 12 . . . in., weight . . . 40.47 . . . lbs./ft. Wall thickness or gauge No. . . 365 . . .									
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS:		From 92 . . . ft. to . . . 108 . . . ft., From ft. to ft. From ft. to ft., From ft. to ft.							
GRAVEL PACK INTERVALS:		From 82 . . . ft. to . . . 110 . . . ft., From ft. to ft. From ft. to ft., From ft. to ft.							
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug Grout Intervals: From . . . 0 . . . ft. to . . . 6 . . . ft., From . . . 6 . . . ft. to . . . 76 . . . ft., From . . . 76 . . . ft. to . . . 82 . . . ft.							
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage None known							
Direction from well?		How many feet?							
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS				
0	3	Topsoil	108	110	Clay				
3	7	Clay, silty							
7	25	Sand and gravel, fine, medium, coarse							
25	26	Clay, brown							
26	41	Sand and gravel, fine, medium, coarse							
41	48	Clay, brown							
48	74	Sand and gravel, fine, medium							
74	83	Clay, brown							
83	93	Clay, brown with sand and gravel							
93	102	Sand and gravel, fine, medium with clay streak at 98'							
102	104	Clay, brown							
104	108	Sand and gravel, fine, medium							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) . . . 12/30/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. . . . 185 This Water Well Record was completed on (mo/day/yr) . . . 1/5/99 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>David W. Clark</i>									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									