

1 LOCATION OF WATER WELL: County: Barton		Fraction 1/4 1/4 CW 1/4 SE 1/4	Section Number 2	Township No. T 19 S	Range Number R 14 ☐ E ☒ W																																																						
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 4 1/4 miles north and 1 1/2 miles west of Great Bend			Global Positioning System (GPS) information: Latitude: 38.4233 (in decimal degrees) Longitude: -98.83908 (in decimal degrees) Elevation: unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																								
2 WATER WELL OWNER: Great Bend Feeding, Inc. RR#, Street Address, Box #: 355 NW 30 Ave. City, State, ZIP Code : Great Bend, KS 67530																																																											
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="display: inline-table; border-collapse: collapse;"><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px; text-align: center;">X</td></tr></table> E S -----1 mile-----					X	4 DEPTH OF COMPLETED WELL 91.2 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 36.8 ft. below land surface measured on mo/day/yr 8/5/10 Pump test data: Well water was <u>not checked</u> ft. after _____ hours pumping _____ gpm EST. YIELD <u>unknown</u> gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 24 in. to 90 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																					
	X																																																										
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 65 ft., Diameter _____ in. to _____ ft., Diameter _____ in. to _____ ft. Casing height above land surface 14 in., Weight 19.75 lbs./ft., Wall thickness or gauge No. .616 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☒ Stainless Steel ☐ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☒ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 65 ft. to 90 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 20 ft. to 90 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																											
6 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From 0 ft. to 2 ft., From 2 ft. to 20 ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None known Direction from well _____ Distance from well _____																																																											
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0</td><td>5</td><td>Topsoil</td><td></td><td></td><td>with gravel, fine to medium, clay streaks, tan, thin, soft</td></tr><tr><td>5</td><td>8</td><td>Clay, gray, hard</td><td></td><td></td><td></td></tr><tr><td>8</td><td>16</td><td>Clay, tan, hard</td><td>89</td><td>90</td><td>Limestone, yellow, soft</td></tr><tr><td>16</td><td>26</td><td>Clay, brown, hard</td><td></td><td></td><td></td></tr><tr><td>26</td><td>42</td><td>Clay, tannish brown, soft, silty</td><td></td><td></td><td></td></tr><tr><td>42</td><td>46</td><td>Clay, brown, soft, with sand, medium to very fine, loose streaks</td><td></td><td></td><td></td></tr><tr><td>46</td><td>50</td><td>Clay, tan, soft, silty, with sand, coarse to very fine and gravel, fine, loose, clean</td><td></td><td></td><td></td></tr><tr><td>50</td><td>89</td><td>Sand, coarse to very fine, loose, clean,</td><td></td><td></td><td></td></tr></tbody></table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	5	Topsoil			with gravel, fine to medium, clay streaks, tan, thin, soft	5	8	Clay, gray, hard				8	16	Clay, tan, hard	89	90	Limestone, yellow, soft	16	26	Clay, brown, hard				26	42	Clay, tannish brown, soft, silty				42	46	Clay, brown, soft, with sand, medium to very fine, loose streaks				46	50	Clay, tan, soft, silty, with sand, coarse to very fine and gravel, fine, loose, clean				50	89	Sand, coarse to very fine, loose, clean,			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																						
0	5	Topsoil			with gravel, fine to medium, clay streaks, tan, thin, soft																																																						
5	8	Clay, gray, hard																																																									
8	16	Clay, tan, hard	89	90	Limestone, yellow, soft																																																						
16	26	Clay, brown, hard																																																									
26	42	Clay, tannish brown, soft, silty																																																									
42	46	Clay, brown, soft, with sand, medium to very fine, loose streaks																																																									
46	50	Clay, tan, soft, silty, with sand, coarse to very fine and gravel, fine, loose, clean																																																									
50	89	Sand, coarse to very fine, loose, clean,																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 8/5/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 8/10/10 under the business name of Clarke Well & Equipment, Inc. by (signature) _____ INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																											