

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Barton		Fraction NE 1/4 NE 1/4 NE 1/4 NE 1/4	Section Number 36	Township No. T 19 S	Range Number R 14 ☐ E ☒ W																																																																		
Street/Rural Address of Well Location: if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 129'S x 32'W of 10th Street and S Patton Rd intersection			Global Positioning System (GPS) information: Latitude: 38.361325 (in decimal degrees) Longitude: 98.811467 (in decimal degrees) Elevation: 1867 Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☒ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																				
2 WATER WELL OWNER: US EPA Region 7 RR#, Street Address, Box #: 11201 Renner Blvd. City, State, ZIP Code : Lenexa, KS 66219																																																																							
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="margin: auto; border-collapse: collapse;"> <tr> <td style="width: 20px; height: 20px;"></td> <td style="width: 20px; height: 20px;"></td> <td style="width: 20px; height: 20px; text-align: center;">X</td> </tr> <tr> <td style="text-align: center;">NW</td> <td style="text-align: center;">NE</td> <td style="text-align: center;">E</td> </tr> <tr> <td style="width: 20px; height: 20px;"></td> <td style="width: 20px; height: 20px;"></td> <td style="width: 20px; height: 20px;"></td> </tr> <tr> <td style="text-align: center;">SW</td> <td style="text-align: center;">SE</td> <td style="text-align: center;">S</td> </tr> </table> W E S -----1 mile-----				X	NW	NE	E				SW	SE	S	4 DEPTH OF COMPLETED WELL 88 ft. Depth(s) Groundwater Encountered (1) <u>13</u> ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL _____ ft. below land surface measured on mo/day/yr _____ Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm EST. YIELD _____ gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter <u>8</u> in. to _____ ft. and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☒ Monitoring well MW-104-D Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☐ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☐ Yes ☐ No																																																									
		X																																																																					
NW	NE	E																																																																					
SW	SE	S																																																																					
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded Casing diameter <u>2.375</u> in. to _____ ft. Diameter _____ in. to _____ ft. Diameter _____ in. to _____ ft. Casing height above land surface <u>6</u> in. Weight _____ lbs./ft. Wall thickness or gauge No. <u>SCH 40 PVC</u> TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From <u>78</u> ft. to <u>88</u> ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From <u>74</u> ft. to <u>78</u> ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft.																																																																							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From <u>3</u> ft. to <u>79</u> ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well _____																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>5</td> <td>Silty Clay, Dk. Brown, Stiff</td> <td>42</td> <td>51</td> <td>Clay</td> </tr> <tr> <td></td> <td></td> <td>Low Plasticity, Moist</td> <td>51</td> <td>62</td> <td>Sand, Tan, Loose, Poorly Graded.</td> </tr> <tr> <td></td> <td></td> <td>Fine Sand Trace</td> <td></td> <td></td> <td>Med. Grained, Wet, Some Gravel</td> </tr> <tr> <td>5</td> <td>9</td> <td>Silty Sand, Tan, Loose, Fine,</td> <td>62</td> <td>77</td> <td>Clay</td> </tr> <tr> <td></td> <td></td> <td>Poorly Graded, Moist</td> <td>77</td> <td>90</td> <td>Sand, Brown, Loose, Well Graded</td> </tr> <tr> <td>9</td> <td>21</td> <td>Sand, Tan, Loose, Well Graded,</td> <td></td> <td></td> <td>Coarse Grained, Wet, Some Gravel</td> </tr> <tr> <td></td> <td></td> <td>Meduim, Moist, Some Fines</td> <td>90</td> <td>93</td> <td>Clay</td> </tr> <tr> <td>21</td> <td>26</td> <td>Clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>26</td> <td>42</td> <td>Sand, Tan, Loose, Well Graded</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>Med Grained, Wet, Some Silt</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	5	Silty Clay, Dk. Brown, Stiff	42	51	Clay			Low Plasticity, Moist	51	62	Sand, Tan, Loose, Poorly Graded.			Fine Sand Trace			Med. Grained, Wet, Some Gravel	5	9	Silty Sand, Tan, Loose, Fine,	62	77	Clay			Poorly Graded, Moist	77	90	Sand, Brown, Loose, Well Graded	9	21	Sand, Tan, Loose, Well Graded,			Coarse Grained, Wet, Some Gravel			Meduim, Moist, Some Fines	90	93	Clay	21	26	Clay				26	42	Sand, Tan, Loose, Well Graded						Med Grained, Wet, Some Silt			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																		
0	5	Silty Clay, Dk. Brown, Stiff	42	51	Clay																																																																		
		Low Plasticity, Moist	51	62	Sand, Tan, Loose, Poorly Graded.																																																																		
		Fine Sand Trace			Med. Grained, Wet, Some Gravel																																																																		
5	9	Silty Sand, Tan, Loose, Fine,	62	77	Clay																																																																		
		Poorly Graded, Moist	77	90	Sand, Brown, Loose, Well Graded																																																																		
9	21	Sand, Tan, Loose, Well Graded,			Coarse Grained, Wet, Some Gravel																																																																		
		Meduim, Moist, Some Fines	90	93	Clay																																																																		
21	26	Clay																																																																					
26	42	Sand, Tan, Loose, Well Graded																																																																					
		Med Grained, Wet, Some Silt																																																																					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>08/21/2013</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>614</u> This Water Well Record was completed on (mo/day/year) <u>09/13/2013</u> under the business name of <u>TSE</u> by (signature) <u>[Signature]</u>																																																																							
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send one copy to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367 Telephone 785-296-3524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html																																																																							