

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: <u>Bartlesville</u>		SE 1/4 SE 1/4 SE 1/4		5		T 19 S		R 15 E/W	
Distance and direction from nearest town or city street address of well if located within city? 2 south 1/2 east of Albert, Ks.									
2 WATER WELL OWNER:		Edward Miller							
RR#, St. Address, Box # :		1524 Cherry Lane							
City, State, ZIP Code :		Great Bend, Ks. 67530							
		Board of Agriculture, Division of Water Resources Application Number: 673							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 176 ft. ELEVATION:							
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.							
		WELL'S STATIC WATER LEVEL 92. ft. below land surface measured on mo/day/yr . 5-16-92.							
		Pump test data: Well water was ft. after hours pumping gpm							
		Est. Yield NA gpm: Well water was ft. after hours pumping gpm							
		Bore Hole Diameter 10. in. to 176 ft., and in. to ft.							
		WELL WATER TO BE USED AS:							
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well							
		Was a chemical/bacteriological sample submitted to Department? Yes.....No. <u>X</u>; If yes, mo/day/yr sample was submitted							
		Water Well Disinfected? Yes <u>hth</u> No							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued . . <u>X</u> . . Clamped 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded 2 PVC 4 ABS 7 Fiberglass Threaded.							
Blank casing diameter 5 in. to 136 ft., Dia. in. to ft., Dia. in. to ft.									
Casing height above land surface 2' in., weight SDR 21 lbs./ft. Wall thickness or gauge No.									
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 <u>Saw cut</u> 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)							
SCREEN-PERFORATED INTERVALS:		From 136 ft. to 176 ft., From ft. to ft. From ft. to ft., From ft. to ft.							
GRAVEL PACK INTERVALS:		From 20 ft. to 54 ft., From 62 ft. to 176 ft. From ft. to ft., From ft. to ft.							
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other .. <u>hole plug</u> Grout Intervals: From ... 3 ft. to ... 20 ft., From ... 54 ft. to ... 62 ft., From ft. to ft.							
What is the nearest source of possible contamination:		10 <u>Livestock pens</u> 14 Abandoned water well 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage							
Direction from well?		<u>West</u> How many feet? <u>80</u>							
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS				
0	5	Top soil	138	142	Sand with clay				
5	20	Brown clay	142	151	Gray clay				
20	35	White rock and gray clay	151	157	Brown sand rock				
35	54	Shale	157	177	Sand rock with clay streaks.				
54	62	Shale, hard rock							
62	71	White clay							
71	82	Brown clay							
82	87	Light brown clay							
87	92	White clay, fire clay							
92	97	White clay little sand rock							
97	102	White, brown clay with shale							
102	105	White and brown clay							
105	110	White clay streaks of sand rock							
110	117	White and brown clay							
117	138	White clay, shale							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-16-92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 .. This Water Well Record was completed on (mo/day/yr) 6-3-92 under the business name of <u>Rosencrantz-Bemis</u> by (signature) <u>Fredrick Redson</u>									